




# Building Specific Work Plan Addendum

811 East Arques Avenue  
Sunnyvale, California

# Certification

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I have no personal knowledge that the information submitted is other than true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

A handwritten signature in black ink that reads 'J. Wesley Hawthorne'.

-----  
J. Wesley Hawthorne

\_\_\_\_13 September 2022\_\_\_\_

Date

## Table of Contents

LIST OF TABLES .....	4
LIST OF FIGURES .....	5
LIST OF APPENDICES .....	6
LIST OF ACRONYMS AND ABBREVIATIONS .....	7
1. Introduction .....	9
1.1 Purpose.....	9
1.2 Work Plan Organization.....	9
1.3 Property Background.....	10
1.4 Vapor Intrusion Investigation Prior to Redevelopment .....	11
2. Building Specific Background .....	12
2.1 Communication with Building Owners/Managers .....	12
2.2 Relevant Groundwater Sampling Data Summary.....	13
2.3 Pre-Survey Assessment .....	14
3. Building Survey Results.....	15
3.1 Building Use.....	15
3.2 Building Occupancy .....	15
3.3 Characteristics .....	15
3.4 Factors Impacting Indoor Air Quality .....	16
3.4.1 Observations .....	16
3.4.2 Building Construction.....	16
3.5 Summary of Potential Vapor Migration Pathways.....	16
3.5.1 Subsurface Structures, Utilities and Floor Drains .....	16
3.5.2 Non-ventilated Spaces .....	17
3.5.3 Heating and Cooling Sources .....	17
3.5.4 Cracks .....	17
3.6 Inventory of Potential Indoor Chemical Sources.....	18
3.7 Ventilation Assessment .....	18
3.7.1 Vestibules.....	20
3.7.2 Staff Offices .....	20

3.7.3	Sales Floor .....	20
3.7.4	Storage/Receiving Area.....	20
4.	Building Specific Conceptual Site Model and Exposure Pathways .....	22
4.1	Conceptual Site Model .....	22
4.2	Sources of VOCs.....	22
4.2.1	Occupational Sources.....	23
4.2.2	Volatilization from Subsurface into the Building .....	23
4.2.3	Background Sources.....	24
4.3	Chemicals of Concern .....	24
4.4	Migration Pathway Analysis .....	24
4.5	Exposure Pathways and Receptors.....	25
4.6	Evaluation of Data Gaps .....	26
5.	Sampling Plan .....	27
5.1	Sample Locations.....	27
5.2	Vapor Pin Installation .....	28
5.3	Sewer Cleanout Sampling Preparation.....	28
5.4	Sample Equipment and Collection .....	29
5.4.1	Sewer Gas Sample Collection.....	29
5.4.2	Sub-slab Soil Gas Sample Collection .....	30
5.4.3	Quality Control Samples.....	30
5.5	Sample Handling and Analysis.....	30
5.6	Schedule .....	31
6.	References .....	32

## TABLES

## FIGURES

## APPENDICES

## ABBREVIATIONS



**LIST OF TABLES****TABLE**

<u>NO.</u>	<u>TITLE</u>
1	HVAC System Details by Ventilation Zone
2	TCE Concentrations in Outdoor Air
3	Sampling Locations and Analysis
4	Sub-Slab Soil Gas and Sewer Gas Evaluation Criteria

**LIST OF FIGURES****FIGURE**

<b><u>NO.</u></b>	<b><u>TITLE</u></b>
1	Site Location
2	Historical Site Plan
3	Current Site Layout
4	Building Floor Plan
5	RTU Layout
6	Enlarged RTU Layout
7	Proposed Sampling Locations
8	Waste and Vent Riser Diagram

**LIST OF APPENDICES**

<b><u>APPENDIX</u></b>	<b><u>TITLE</u></b>
<b>A</b>	Relevant Groundwater Figures
<b>B</b>	811 East Arques Commercial Indoor Air Survey
<b>C</b>	811 East Arques Hazardous Materials Business Plan
<b>D</b>	811 East Arques Preventative Maintenance Checklist
<b>E</b>	Standard Operating Procedure – Vapor Pin Installation
<b>F</b>	Standard Operating Procedure – Soil Gas Sampling
<b>G</b>	City of Sunnyvale Sewer Utility Map

**LIST OF ACRONYMS AND ABBREVIATIONS**

<b><u>ACRONYM</u></b>	<b><u>DESCRIPTION</u></b>
1,1-DCA	1,1-dichloroethane
1,1-DCE	1,1-dichloroethene
1,1,1-TCA	1,1,1-trichloroethane
ASAO	Administrative Settlement Agreement and Order on Consent
ASHRAE	American Society of Heating, Refrigerating and Air-Conditioning Engineers
BAAQMD	Bay Area Air Quality Management District
cis-1,2-DCE	cis-1,2-dichloroethene
COC	Chemical of Concern
EPA	United States Environmental Protection Agency
HMBP	Hazardous Materials Business Plan
HVAC	Heating, Ventilation, and Air Conditioning
Locus	Locus Technologies
µg/L	Micrograms per liter
O&M	Operations and Maintenance
PCE	tetrachloroethene
Philips	Philips Semiconductors Inc.
PM	Preventative Maintenance
Property	811 East Arques Avenue
QAQC	Quality Assurance Quality Control
RTU	Roof Top Unit
sq ft	Square Feet
SDS	Safety Data Sheet
SOP	Standard Operating Procedure

TCE	trichloroethene
trans-1,2-DCE	trans-1,2-dichloroethene
VI	Vapor Intrusion
VOCs	Volatile Organic Compounds

## 1. Introduction

Locus Technologies (Locus) has prepared this Building Specific Work Plan Addendum (Addendum) for the building located at 811 East Arques Avenue in Sunnyvale, California (Property). This document accompanies the Final Indoor Air/Vapor Intrusion Removal Site Evaluation and any Necessary Removal Action Work Plan (Vapor Work Plan) dated 29 May 2020 and provides supplemental building specific information and vapor intrusion (VI) sampling recommendations for the Property as overseen by the United States Environmental Protection Agency (EPA).

### 1.1 Purpose

The purpose of this Addendum is to provide supplemental building specific information as it relates to potential vapor intrusion, document the building survey conducted at the Property, and evaluate the results of the building survey through a conceptual site wide model. Based on this analysis, this Addendum ultimately makes sampling recommendations for the Property.

### 1.2 Work Plan Organization

This Addendum provides a building specific approach for VI evaluation at the Property beginning with a discussion of building-specific background in Chapter 2. The results of the building survey are discussed in Chapter 3. The building-specific conceptual side wide model is developed in Chapter 4. The building-specific sampling plan is discussed in Chapter 5. Groundwater figures relevant to the Property are included in Appendix A. The completed building survey form is included in Appendix B. The Hazardous Material Business Plan (HMBP) for the Property owner/occupant is included in Appendix C. The building Heating, Ventilation,

and Air Conditioning (HVAC) system preventative maintenance checklist being implemented by the property owner/occupant is found in Appendix D.

### 1.3 Property Background

The Property is located in Sunnyvale, California and is within the Signetics Site (Figures 1 and 2). It is undergoing groundwater remediation and vapor intrusion investigations as described in the Vapor Work Plan. One building currently exists at 811 East Arques Avenue, towards the southeast side of the Property, as seen in Figure 2. Before 2005, a building was located on the west side of Property. Details on the usage of each building is described below.

From 1964–2005, the Property was used by Philips Semiconductors, Inc. (Philips) as part of a semiconductor manufacturing facility, which used various organic solvents. In 1982, a source area was identified as a leak in an underground waste solvent storage tank west of the former 811 East Arques building. After this source was identified, a review of potential source areas at the site was completed, and as a result of this investigation, a second source area was identified near wastewater neutralization tanks on the north side of the former building. Locations of these sources as seen in Figure 2. The tanks were removed in 1982; impacted soils were excavated in 1982 and 1987. Groundwater extraction and treatment in the A-aquifer also began in 1982.

In 2005, the Property was sold to Lowe's Companies Inc. and the former manufacturing facility building was demolished. Redevelopment activities occurred throughout the Property. It currently contains a commercial slab on-grade building of approximately 135,000 square feet (sq ft) at the southeast side of the Property, which operates as a hardware and home improvement store. A parking lot covers the former building foot print. A current building site plan can be seen in Figure 3.

The Property parking lot is adjacent to the former 811 Arques Extraction Trench along the north side of the property. Bioremediation efforts began near the trench in 2016.

#### 1.4 Vapor Intrusion Investigation Prior to Redevelopment

A VI investigation was conducted in 2002 at the former building. The building was evaluated using flux chambers and indoor air samples (Locus, 2003). This evaluation of the vapor intrusion pathway demonstrated that indoor inhalation exposure through that pathway was within acceptable limits and not expected to cause unacceptable risks or hazards. Because other sources were present and contributing to indoor air concentrations, it was recommended that sump covers be sealed to minimize any potential contribution from vapor intrusion. This building was demolished in 2005 and is not directly relevant to the current building on the Property. This investigation is referenced for historical completeness only.



## 2. Building Specific Background

The 811 Arques Signetics Property was used by Philips Semiconductors, Inc. for the research, development, and manufacturing of semiconductors. The following is a timeline of notable events regarding the Property and current building: Signetics Corporation, which later became Philips, operated a manufacturing facility at the Property starting in 1964. The manufacturing was conducted in a now-demolished building on the west side of the Property.

- ◊ In 1982, two source areas were identified as a result of an investigation stemming from leaking storage tanks of various organic solvents. These source areas were located near the former building.
- ◊ In 2005, the property was sold to Lowe's Companies, Inc. The former building was demolished and the land was redeveloped. A new building was constructed at the southeast side of the Property and currently operates as a home-improvement hardware store. No VI investigations have been conducted for the current building.

### 2.1 Communication with Building Owners/Managers

The following is a summary of communications with the current building owners or on-site facilities managers at the Property. As part of the ongoing groundwater cleanup activities in this area, there are several monitoring and extraction wells installed on the Property, which have been in use since the 1990s. Bioremediation efforts at the Arques Extraction Trench have also been ongoing since 2016, with property owner acknowledgment and approval. As such, communications on the environmental status of the Property have been ongoing for many years. The summary below includes communications relevant to vapor intrusion issues:

- ◇ In February 2020, the real estate manager was informed of the beginning of bioremediation work at the Extraction Trench. An info sheet regarding field activities, including building survey and air sampling, was also provided.
- ◇ In June 2021, the store manager and the corporate real estate manager were contacted by Locus to schedule a building survey.
- ◇ In October 2021, Locus met virtually with the real estate manager and his team to answer questions regarding the building survey. Approval was granted for Locus to schedule the building survey.
- ◇ In February 2022, Locus met with the operations manager of the Lowe's store at 811 East Arques and conducted a commercial building survey with oversight from an EPA-representative (APTIM).

## 2.2 Relevant Groundwater Sampling Data Summary

The Property is located on top of a shallow "A" groundwater aquifer. The current building is hydraulically upgradient of the former manufacturing facility building and historical sources as indicated by the groundwater contour map seen in Appendix A and locations specified in Figure 2.

Groundwater monitoring wells nearby the current building include S157A, S001A, and S024A. The TCE contour map in Appendix A shows concentrations downgradient (S024A) and upgradient (S157A) of the building are 14 micrograms per liter ( $\mu\text{g/L}$ ) in 2020. Well S001A, cross-gradient of the property, has a lower TCE concentration of 4.8  $\mu\text{g/L}$ .

Higher concentrations of TCE are located at the north end of the Property near the historical source, however because the current building is hydraulically upgradient of this area

by at least 300 feet, those concentrations are expected to have limited impact on VI levels in the building.

### 2.3 Pre-Survey Assessment

Typically, one goal of the commercial building survey is to identify potential sampling locations for passive indoor air sampling. However, the 811 East Arques building operates as a home improvement and hardware store and contains many products (such as glues, paints, degreasers, etc) that would normally be flagged during a routine commercial building survey. Due to the numerous products containing volatile organic compounds (VOCs) in the building, it would be difficult to determine which compounds of interest originated from vapor intrusion and which were present in the building due to off-gassing by the various products in the store. This concern was communicated to EPA by Locus during a kick-off call on 12 January 2022. Thus, it was concluded that indoor air sampling would not be an effective approach for this building due to confounding chemical sources, and vapor sub slab sampling will be planned moving forward.

Furthermore, given the chemical inventory available in the store, it was concluded that ventilation provided by the HVAC system would be most relevant factor in evaluating potential exposure. Ventilation specifically in office, classroom, and break room spaces would be of particular interest as that would be where building occupants would spend most of their time, and also because there is greater potential for indoor chemical accumulation in these smaller spaces, compared to the open warehouse. Because of this focus, the building survey template in the Vapor Work Plan was modified to remove the formal chemical inventory as agreed to in the 12 January 2022 meeting, and a review of safety data sheets and/or a HMBP would be acceptable instead.

### 3. Building Survey Results

On 15 February 2022, Locus personnel met with the operations manager of the Lowe's Home Improvement store at the Property for a formal commercial building survey to observe conditions related to indoor air quality and the potential for vapor intrusion. The completed survey form can be seen in Appendix B.

#### 3.1 Building Use

The 811 East Arques building is a single level warehouse with office space that conducts business as a home improvement and hardware store.

#### 3.2 Building Occupancy

Operating hours span seven days a week, Monday through Saturday from 6:00AM to 9:00PM, and Sunday from 8:00AM to 8:00PM. Most customers generally spend short periods of time under one hour on the premises. The building is occupied almost all the time as there are two shifts for staff. Day-time salaried staff are typically onsite for up to 50 hours per week and night-time staff are onsite for up to 40 hours per week. Staff typically spend 2–3 hours per day in the office area, which is an area of concern due to potentially lower air flow. The building is closed and unoccupied Friday and Saturday nights.

#### 3.3 Characteristics

The building at the Property is a single-store, slab-on-grade concrete building with an approximate area of 135,000 sq ft. This includes an outdoor covered garden center with shaded structures and an indoor receiving and storage area. There is no crawlspace, basement, or attic.

The sections of the building include a sales floor, a covered outdoor garden center, a receiving

and storage area, offices, classrooms, a break room for staff, and men and women's restrooms. The sales floor and garden center occupy the majority of the building. A floor plan of the building can be found in Figure 4.

The building foundation was constructed at the time of property redevelopment in 2005 and contains a moisture vapor barrier under concrete slab.

### 3.4 Factors Impacting Indoor Air Quality

#### 3.4.1 *Observations*

The building appears well-ventilated in general. No stagnant air was observed during the commercial building survey. Supply and return grilles exist in each room and the HVAC system is constantly on during building operating hours. Additionally, there is a sliding door to the garden area that is open during operating hours. The temperature of the building during operating hour is set to hold between 68° – 73° Fahrenheit, which is typically warmer than outdoor air during the winter time.

#### 3.4.2 *Building Construction*

The building materials are mostly comprised of concrete. It has an at-grade garage and an attached electrical room. The ceiling in the sales floor part of the building has a height of 31 feet while the office and classroom spaces have a ceiling height of 10 feet. There are also twenty roof top units (RTU) responsible for ventilation in the building.

### 3.5 Summary of Potential Vapor Migration Pathways

#### 3.5.1 *Subsurface Structures, Utilities and Floor Drains*

The building foundation is slab-on-grade, and thus does not have a basement. The building contains some utilities that penetrate the slab in the electrical room, which may be

conduits for soil vapor, though they appeared sealed. Migration pathways such as floor drains can be found in the janitorial closet, the men's and women's restroom areas. There is one floor drain in each of these rooms.

Based on City of Sunnyvale utility maps, it was determined that the Property is connected to Sunnyvale's main sewer line via a lateral off of Wolfe Road, on the western side of the property. The utility map shows a depth from manhole to main sewer line of 10.7 feet, as seen in Appendix G. Water elevations for three wells, S024A, S134A, and S001A, were pulled from Locus' 2021 Annual Groundwater Monitoring Report for OOU and Signetics (Locus, 2022). The depth to groundwater for those three wells were 9.26 ft bgs, 8.47 ft bgs, and 7.80 ft bgs respectively. This suggests that the water table is above the City sewer line and the groundwater plume and vapor could impact the City sewer line. Because the Property lateral is connected to this City sewer, the lateral could be a conduit for vapors to migrate to the building. The lateral connects to a 4-inch sewer line that runs under the janitorial and restroom areas as seen in Figure 8.

### *3.5.2 Non-ventilated Spaces*

The building appears well-ventilated. Either a supply grille, a return grille, or both exists in each room of the building, including janitorial closets. No stagnant air was noticed during the commercial building survey.

### *3.5.3 Heating and Cooling Sources*

The building uses RTUs capable of heating and cooling. See the ventilation assessment in Section 3.7 for more details.

### *3.5.4 Cracks*

Cracks in the foundation slab, both sealed and unsealed were noted. In general, exposed foundation slab had sealed cracks. Metal bolts, used to secure scaffold frames and shelves in

the sales floor, are drilled into the concrete slab and some have been removed due to reorganization. These drilled holes do not appear to penetrate the slab.

### 3.6 Inventory of Potential Indoor Chemical Sources

The Lowe's Home Improvement and Hardware store at the Property stocks over 40,000 items. A Safety Data Sheet (SDS) database is available in-store and printouts of each product are available. The database is searchable by product name, but not by product components or ingredients. Therefore, a comprehensive review of the chemical inventory would require an extensive manual review of each product SDS. In the interest of proceeding expeditiously with this evaluation, and given the high likelihood of chemicals of concern (COCs) being present in at least some of products, this database was not exhaustively searched. Should confounding factors arise, the database can be reviewed in the future.

A HMBP is also available, which details chemical storage and hazardous waste accumulation areas. A copy of the HMBP is available in Appendix C. Although the HMBP does not describe any specific storage of COCs or solvents at the Property, the storage area near the northeast corner of the building exterior includes spill cleanup waste, which may originate from other products sold in the store.

### 3.7 Ventilation Assessment

According to the Property's Facilities Asset Program Analyst, the building is compliant with the American Society of Heating, Refrigerating and Air-Conditioning Engineers (ASHRAE) Standard 62. This standard specifies minimum ventilation rates of supplied outdoor air determined by area of each zone and occupancy in order to minimize potential adverse health effects. The HVAC system preventative maintenance (PM) is completed quarterly. An example

PM checklist is found in Appendix B. Air filters are changed quarterly; coil cleaning and belt is changed annually. No stagnant air was noted in the building during the commercial building survey.

The building is divided into five zones serviced by 20 RTUs capable of heating and cooling. The 20 RTUs are Lennox LGA120H, 180H, or 240H package units capable of heating and cooling. The model (i.e. power output) of the unit depends on the ventilation zone the system services. There is also one LCA036H unit only capable of cooling used to cool the computer room. These RTUs have outdoor air intakes and economizers, which have been set by the facility to meet ASHRAE standards. See Table 1 for details on HVAC system zones, unit models, outdoor air flow, and economizers. See Figure 5 for a RTU layout.

The RTUs are controlled by a building automation system that is programmed with three modes: Customer Occupied, Employee-only Occupied, and Unoccupied. During Customer Occupied times (store hours), the HVAC system fan is on continuously, providing outdoor air adhering to ASHRAE standards, and maintaining a temperature between 68° – 73° Fahrenheit. During Employee-only Occupied times (no customers), the HVAC system fan operates automatically to maintain a temperature between 67° – 73° Fahrenheit. During Unoccupied times, the HVAC system fan operates automatically to maintain a temperature between 65° – 78° Fahrenheit. Outdoor air intakes rates are seen in Table 1.

Additionally, there is a sliding door between the indoor sales floor and the outdoor garden area that remains open during customer occupied store hours. There are also receiving bays where trucks deliver products and supplies which are opened occasionally.

Information for specific areas of the building is provided below for the vestibules, staff offices, sales floor, and storage/receiving area (see Figure 5).



### *3.7.1 Vestibules*

The vestibule zone is 1,380 square feet in area and is serviced by the RTU-2 (LENNOX LGA120H) HVAC system, which is capable of both heating and cooling. This zone encompasses corridors, restrooms, and support areas near the entrance of the building. See Figure 6 for a mechanical drawing of the RTU-2 HVAC system, including supply and return ducts and grilles.

### *3.7.2 Staff Offices*

The staff offices are 3,764 sq ft in area and serviced by the RTU-3 (LENNOX LGA120H) HVAC system, which is capable of both heating and cooling. This zone encompasses office spaces, computer rooms, classrooms, a break room, and associated corridors. The computer room, while part of the office zone, is serviced separately by RTU-1 (LENNOX LCA036H) only capable of cooling. A mechanical drawing of the RTU-3 HVAC system, including supply and return ducts and grilles are shown in Figure 6. Each room in this office space has either a supply grille or return grille and often both.

### *3.7.3 Sales Floor*

The sales floor is 117,347 sq ft in area and serviced by fifteen RTUs (LGA240H and LGA180H) capable of heating and cooling. There is no duct system in the sales floor area, there are only straight duct drops below each RTU. See Figure 5 for a rooftop unit layout diagram. There is also a sliding door that opens to an outdoor garden center (not included in the square footage) that remains open and provides additional outdoor air ventilation during open store hours.

### *3.7.4 Storage/Receiving Area*

The storage/receiving area is 10,082 sq ft in area and serviced by two LENNOX LGA180H units (RTU-19, 20), which are capable of both heating and cooling. There is no duct system for the storage/receiving area, there are only straight duct drops below each RTU. Refer to Figure

5 for the rooftop unit layout diagram. There are three bay doors for trucks to deliver shipments. Two of these bay doors are actively used, while one of the bay doors has a truck container permanently parked in front of the open door and is used for storage. Furthermore, there is a walled receiving office and an enclosed electrical space in this area; however, neither the office nor electrical space has ceilings and so they receive ventilation from the two RTUs servicing this zone.

## 4. Building Specific Conceptual Site Model and Exposure Pathways

### 4.1 Conceptual Site Model

A site conceptual model identifies sources, COCs, potential exposure pathways and receptors. This building-specific conceptual model comprises of written descriptions that illustrate the current understanding of potential sources of VOCs indoors and how the VOCs may be transported from the point of release to the point where humans can breathe them.

### 4.2 Sources of VOCs

For an occupant of this building, potential inhalation exposure may have a number of sources. For indoor exposure, sources could be one or a combination of the following:

1. Occupational sources from the usage and storage of chemicals in the building (e.g. paints, glues, cleaning agents, and other home improvement products) or introduced from occupants' homes or occupations (e.g. dry-cleaned clothing, smoking, occupational hazards).
2. Volatilization from the subsurface (soil and/or groundwater) into the building structure through migration pathways,
3. Background concentrations contributed by outdoor air moving into the building through opened doors, the windows, or through the HVAC systems. This outdoor air contribution can include concentrations from emissions from industries (e.g. drycleaners, combustion processes, etc).

#### 4.2.1 *Occupational Sources*

Concentrations of volatile chemicals in indoor air could be affected by the use of consumer products and personal habits. For example, VOCs in cleaning agents, room deodorizers, dry cleaned clothing, cigarette smoke, and vehicle exhaust can all affect indoor air quality. Certain adhesives, spot removers, paint removers, scented candles, and degreasing products can also be a potential source of TCE found in indoor air. The Lowe's home improvement and hardware store at the Property carries over 40,000 products and many contain VOCs. To counteract the unavoidable presence of VOCs, proper ventilation adhering to ASHRAE standards becomes a necessity.

#### 4.2.2 *Volatilization from Subsurface into the Building*

VOCs may migrate upward via unsealed cracks in the floors or subsurface structures such as utility piping, and enter buildings in the vapor phase. These vapors may be present in the subsurface as a result of volatilization from the impacted groundwater or soils, where the chemicals may partition into the vapor phase, and then move by advection or diffusion through open pores in the soil. Since the shallow "A" Aquifer has been observed at 6 to 15 feet below ground surface in monitoring wells located near the Property (Locus, 2021a), there is a potential for volatilization. Unsealed foundation cracks that were not observed are potential migration pathways, in addition to unsealed utility penetrations. Since indoor air testing is confounded by the presence of VOCs from products in the store, soil gas testing is important to determine the magnitude of potential vapor intrusion.

As previously mentioned in Section 3.5.1, the water table appears to be above the main sewer line depth at the Property line, thus the floor drains connected to sewer lines are also potential migration pathways.

#### 4.2.3 *Background Sources*

Emissions from industries (e.g. dry cleaners, combustion processes, etc.), activities (e.g. smoking, use of VOC-containing consumer products), as well as building materials (e.g. insulation, carpeting, paint, etc.) contribute VOCs to the indoor and background air. Background concentrations of VOCs are present in the local and regional outdoor ambient air.

The Bay Area Air Quality Management District (BAAQMD) operates approximately 20 air monitoring stations in the Bay Area. The BAAQMD collects air samples from these stations and analyzes them for VOCs and other airborne chemicals. Outdoor Air Quality Data Reports from these stations is available on the EPA Air Data website. Results have indicated that TCE is detected at very few stations closest to the Property. For results see Table 2.

While TCE has historically and occasionally been detected in outdoor, the Outdoor Air Evaluation conducted in February 2021 suggests that potential hazard due to VOCs in outdoor ambient air is minimal (Locus, 2021b).

#### 4.3 Chemicals of Concern

The list of chemicals of concern for the Signetics site is specified in Section 2.5 of the Vapor Work Plan (Locus, 2020). For reference, the chemicals are 1,1-dichloroethane (1,1-DCA); 1,1-dichloroethene (1,1-DCE); cis-1,2-dichloroethene (cis-1,2-DCE); trans-1,2-dichloroethene (trans-1,2-DCE); Freon 113; 1,1,1-trichloroethane (1,1,1-TCA); TCE; vinyl chloride; chloroform; and tetrachloroethene (PCE).

#### 4.4 Migration Pathway Analysis

Contaminants may volatilize from the groundwater or soil, migrate upward through voids and unsealed cracks in the floors, through dry conduits, or other subsurface structures, and

enter into buildings. Potential receptors in the buildings could inhale these chemical concentrations as they accumulate within a building over time. Of the conditions surveyed at the Property, the floor drains pose a potential as a migration pathway since it is unknown if one-way valves are installed as part of their piping construction. Observable cracks in the foundation slab appeared sealed, but there may be unsealed cracks not detected by the building survey. However, this is a lower potential migration pathway due to the thickness and construction of the slab which contains a moisture vapor barrier.

Many VOCs, including TCE, may be present in outdoor air as shown in Table 2. As such, HVAC systems drawing in outdoor air may inadvertently provide a migration pathway for airborne contaminants. However, air ventilation systems are expected to pose a relatively low potential migration pathway as concluded by the Outdoor Air Evaluation conducted in February 2021 (Locus, 2021b).

It is unclear if these migration pathways contribute to the indoor air quality from the subsurface, therefore further investigation into the specific soil gas VOC concentrations would be appropriate.

## 4.5 Exposure Pathways and Receptors

Inhalation of impacted indoor air by building occupants is the potential exposure pathway being evaluated by the Vapor Work Plan. Potential receptors are persons currently employed at 811 East Arques and their customers. Store hours are Monday through Saturday from 6:00AM to 9:00PM and Sunday from 8:00AM to 8:00PM. Generally, customers visiting the store during these times would spend less than an hour inside the store. Meanwhile, salaried workers spend up to 50 hours per week inside the store. Night-shift workers spend up to 40 hours per week in the store. Typically, the Indoor Air Quality Evaluation Criteria set forth in Table 4 of the Vapor

Work Plan would apply (Locus, 2020). However, since VOCs from products inside the store are a confounding variable with respect to the evaluation of vapor intrusion, sub-slab screening levels defined using EPA's Vapor Intrusion Screening Level calculator will be used. See Section 5 for more details.

#### 4.6 Evaluation of Data Gaps

Data gaps identified in this building-specific conceptual site model include background sources of VOCs that may be difficult to differentiate from vapor intrusion sources. The building contains over 40,000 products, many of which may contribute to background sources of VOCs, making it difficult to determine the true magnitude of subsurface vapor intrusion.

The migration pathways mentioned in Section 4.4 also pose a data gap as it is unknown if all pathways have been identified and inventoried from the building survey. Much of the sales floor is covered by product shelves and floor models, which make identifying cracks in the slab difficult. The concentrations of COCs in the vapor underneath the building slab are also unknown, though expected to be low based on the nearest available groundwater data.

The rate of air exchange into and out of the building may also pose a data gap. However, this risk is minimized as the building adheres to ASHRAE standards during store hours. Conclusions from the Outdoor Air Evaluation minimizes the potential risk in the outdoor air supply.

## 5. Sampling Plan

For this investigation at 811 East Arques, sampling will be focused on the sub-slab soil gas and potential migration pathways. Summa-passivated canisters will be used to sample the soil gas beneath the building from vapor pins as well as a sewer cleanout. The below section summarizes the sample locations, vapor pin installation, sample collection techniques, and evaluation considerations.

### 5.1 Sample Locations

Eight vapor pins are recommended to be installed in order to provide a representative sample of the soil gas beneath the slab. Two vapor pins shall be installed along the north side of the building, in the sales floor area and near the storage/receiving area; these locations are closest to the former source area. Four more vapor pins shall be installed on the sales floor, near the eastern and middle of the building for spatial coverage of the building. Two additional vapor pins shall be installed in the working spaces: one by the water fountains outside the women's restroom and one in the training room.

Additionally, the Property construction drawings show at least six sewer line cleanouts that access the main sewer line which runs under the bathrooms and janitorial closet. Locus will collect a grab sample from a sewer line cleanout to ascertain if impacted sewer lines below the water table are a source of vapor intrusion. On 20 May 2022, Locus performed another building walkthrough and identified a sewer cleanout to sample outside the store, by the gardening center. The sewer cleanout is located at ground level, flush to the concrete grade.

Approximate sampling locations are identified in Figure 7 and seen in Table 3, though locations may change depending on practicality and feedback from Lowe's.



## 5.2 Vapor Pin Installation

Vapor pins will be used to collect soil gas from immediately below the building slab. Vapor pins shall be installed using the 2015 *Advisory Active Soil Gas Investigations* guidance, which was jointly developed by California Department of Toxic Substances Control (DTSC) and California Regional Water Quality Control Board (RWQCB) (EPA, 2015). Before installation, utilities will be cleared as well as reinforcement structures. Following clearance, vapor pins will be installed according to the Locus vapor pin Standard Operating Procedure (SOP) found in Appendix E. Care will be taken to avoid damaging areas with floor tiles by integrating a diamond hole saw among other tools. In areas where the floor may be frequently wet, like the bathroom, the floor cover will be sealed to prevent the cavity being filled up with water over time. Because the moisture barrier is located directly beneath the slab, drilling through the slab to install vapor pins may penetrate the barrier. When vapor pins are decommissioned, the hole will be sealed. The moisture barrier would be repaired by applying sealant deeper than the barrier, creating a seal at the moisture barrier interface. Further details are discussed in the SOP. The floor tiles will be replaced as needed.

## 5.3 Sewer Cleanout Sampling Preparation

The identified sewer cleanout sample location is accessible through an approximately 40-inch riser pipe that is flush-to-grade at sidewalk level. As there is riser, liquids are not in contact with the well cap. In preparation for sampling the sewer cleanout, the cap to the cleanout must be removed and replaced with an inflatable test plug to form a seal. A length of tubing will be installed on the test plug to ensure the sample is collected as close to the junction of the sewer line and riser pipe as possible, while avoiding liquids. Approximately 30 inches of tubing is anticipated for the outdoor sewer clean out location. After the test plug installation,

the sewer gas within the cleanout should be allowed to equilibrate approximately two hours before proceeding with sampling.

## 5.4 Sample Equipment and Collection

Grab samples will be collected from each of the aforementioned sampling locations in passivated one-liter, laboratory-certified clean Summa canisters by qualified field personnel. Canisters are stainless steel containers that are supplied under negative pressure. Once received from the laboratory, a pre-evacuated Summa canister can hold a high vacuum (i.e. > 30 inches of mercury) for up to 30 days. It should be used during this period to ensure appropriate vacuum during sampling.

### 5.4.1 *Sewer Gas Sample Collection*

After the test plug is prepared, sewer gas sampling will be in general accordance with summa canister sampling procedure found in Section 4.5.2 of the Vapor Work Plan (Locus, 2020). In addition, before sampling the sewer gas cleanout, a shut-in test will be implemented and the ambient air within sample tubing will be evacuated.

The 1-minute shut-in test will be conducted on the cannister and flow regulator associated with this sample location to ensure sufficient initial vacuum and that there will be no loss of vacuum during sample collection. After a successful shut-in test in which there is no noticeable loss of vacuum for the entire 1-minute period, the canister will then be attached to the previously installed test plug. The sample tubing will be purged briefly (no more than a few seconds) to remove ambient air from the line. The riser shall not be purged. Thereafter, samples will be collected per the Vapor Work Plan (Locus, 2020) as mentioned above.

#### 5.4.2 *Sub-slab Soil Gas Sample Collection*

Before sub-slab soil gas sampling, a shut-in test, leak test, and purging will be conducted and documented. Purging and sampling will occur within a tracer gas shroud. Detailed procedures and equipment for soil gas sampling are included in Appendix F and are based on guidance from the *Advisory Active Soil Gas Investigations* (EPA, 2015).

#### 5.4.3 *Quality Control Samples*

One field blank and one field duplicate will be collected each sampling day. Additional Quality Control Quality Assurance (QAQC) measures are within Section 4.6 of the Vapor Work Plan (Locus, 2020).

### 5.5 Sample Handling and Analysis

Samples will be labeled and collection documented on a chain of custody consistent with Section 3.3 of the Vapor Work Plan Quality Assurance Project Plan (QAPP) (Locus, 2020). Samples will be submitted to Eurofins Environment Testing Northern California for analysis of site-specific chemicals of concern by USEPA Method TO-15 for all samples. Sub-slab samples will also be analyzed for helium by ASTM D1946, as seen in Table 3.

After soil gas sample results are received, they will be compared with the soil gas screening levels seen in Table 4. The soil gas screening levels were derived applying an attenuation factor of 0.03 to the indoor air screening levels, also seen in Table 4. The indoor air screening values are equivalent to the Vapor Work Plan Table 4 long-term mitigation criteria; however, they are deemed as screening levels because their purpose is to assist in an initial evaluation of sub-slab concentrations. Where long-term criteria were not available for a parameter, short-term criteria were used, as noted.

## 5.6 Schedule

Each sampling location will be sampled twice, at least four months apart, to evaluate temporal variability. It is expected that the upcoming sampling events for proposed locations (as shown in Figure 7) will occur:

- ◊ Installation of vapor pins would occur within 21 days of Work Plan Addendum approval by EPA and approval by building owner, whichever comes last (anticipated third or fourth quarter 2022)
- ◊ First sampling event, concurrent with vapor pin installation, with approval by building owner.
- ◊ Second sampling event, four to six months after first sampling event, with approval by building owner.

Modifications to the above sampling program may be recommended, including potential changes to sampling locations and techniques. Recommendations would be based upon review of sampling results, and would be subject to EPA approval prior to those modifications being implemented.

## 6. References

- Environmental Protection Agency Region 9, 2019, *CERCLA Docket No. 2018-09: Administrative Settlement Agreement And Order On Consent For Focused Feasibility Study, Removal Site Evaluation And Removal Action*, 15 March.
- California Department of Toxic Substances Control, 2020, *Supplemental Guidance: Screening and Evaluating Vapor Intrusion. Draft for Public Comments*. February 2020.
- Locus Technologies, 2003, *Results of Air Monitoring, 811 East Arques Avenue Site, Sunnyvale, California*, 6 January.
- Locus Technologies, 2020, *Final Work Plan: Indoor Air / Vapor Intrusion Removal Site Evaluation and any Necessary Removal Action, Signetics Site, Sunnyvale, California*, 29 May.
- Locus Technologies, 2021a, *Annual Groundwater Monitoring Report, January to December 2020, Signetics Site and Offsite Operable Unit, Sunnyvale, California*, 30 April.
- Locus Technologies, 2021b, *Outdoor Air Evaluation, Triple Site, Signetics Site, and Offsite Operable Unit, Sunnyvale, California*, September 2021

# Tables

**TABLE 1**  
**HVAC SYSTEM DETAILS**  
**BUILDING SPECIFIC WORK PLAN ADDENDUM: 811 EAST ARQUES**  
**SIGNETICS SITE, SUNYVALE, CALIFORNIA**

System Name	RTU-1 (Computer Room)	RTU-2 (Vestibule)	RTU-3 (Office)	RTU Sales Area (4-18)	RTU-19, 20 (Storage/Receiving)
Area (square feet)	N/A	1380	3764	116,170	9820
Outdoor Air (cfm)	200	450	1680	29025	1474
Make/Model	LENNOX LCA036H	LENNOX LGA120H	LENNOX LGA120H	LENNOX LGA240H/180H	LENNOX LGA180H
Economizer	N/A	Fixed Enth (Integrated)	Fixed Enth (Integrated)	Fixed Enth (Non-Integrated)	Fixed Enth (Integrated)
Heating Type	None	Gas Furnace	Gas Furnace	Gas Furnace	Gas Furnace
Cooling Type	Packaged DX	Packaged DX	Packaged DX	Packaged DX	Packaged DX

Note: HVAC System details were compiled from construction drawings provided by Lowe's

**TABLE 2**  
**TCE CONCENTRATIONS IN OUTDOOR AIR**  
**EPA AIR DATA**  
**BUILDING SPECIFIC WORK PLAN ADDENDUM: 811 EAST ARQUES**  
**SANTA CLARA COUNTY, CALIFORNIA**

Station Address	Year	Total Observations	Observations Non-Detected	Mean Concentration ( $\mu\text{g}/\text{m}^3$ )	Max Concentration ( $\mu\text{g}/\text{m}^3$ )
120b N 4th St, San Jose	1986	13	0	1.745	4.409
160 Cuesta Dr., Mountain View	1986	16	1	1.233	3.011
120b N 4th St, San Jose	1987	16	0	1.314	4.194
160 Cuesta Dr., Mountain View	1987	24	6	0.578	1.613
160 Cuesta Dr., Mountain View	1988	23	14	0.255	0.860
1866 W San Carlos St, San Jose	1989	10	7	0.151	0.538
160 Cuesta Dr., Mountain View	1989	24	16	0.181	0.645
1866 W San Carlos St, San Jose	1990	30	22	0.973	15.593
160 Cuesta Dr., Mountain View	1990	24	19	0.110	0.645
1866 W San Carlos St, San Jose	1991	30	30	0.000	0.000
120b N 4th St, San Jose	1991	15	0	0.287	0.430
120b N 4th St, San Jose	1991	30	29	0.018	0.538
160 Cuesta Dr., Mountain View	1991	24	24	0.000	0.000
160 Cuesta Dr., Mountain View	1992	24	24	0.000	0.000
120b N 4th St, San Jose	1992	31	31	0.000	0.000
120b N 4th St, San Jose	1992	31	0	0.156	0.968
1866 W San Carlos St, San Jose	1992	31	31	0.000	0.000
1866 W San Carlos St, San Jose	1993	30	30	0.000	0.000
120b N 4th St, San Jose	1993	30	0	0.072	0.215
120b N 4th St, San Jose	1993	29	28	0.020	0.591
160 Cuesta Dr., Mountain View	1993	24	24	0.000	0.000
1866 W San Carlos St, San Jose	1994	13	12	0.116	1.506
120b N 4th St, San Jose	1994	31	0	0.076	0.269
120b N 4th St, San Jose	1994	29	23	0.113	0.699
160 Cuesta Dr., Mountain View	1994	24	23	0.092	2.205
120b N 4th St, San Jose	1995	30	0	0.095	0.161
120b N 4th St, San Jose	1995	30	18	0.229	0.807
160 Cuesta Dr., Mountain View	1995	22	21	0.020	0.430
120b N 4th St, San Jose	1996	31	0	0.127	1.774
120b N 4th St, San Jose	1996	31	29	0.031	0.538
160 Cuesta Dr., Mountain View	1996	31	30	0.016	0.484
120b N 4th St, San Jose	1997	27	0	0.096	0.645
120b N 4th St, San Jose	1997	30	30	0.000	0.000
160 Cuesta Dr., Mountain View	1997	29	25	0.482	7.581
120b N 4th St, San Jose	1998	29	0	0.089	0.269
120b N 4th St, San Jose	1998	30	30	0.000	0.000
160 Cuesta Dr., Mountain View	1998	30	29	0.016	0.484
120b N 4th St, San Jose	1999	23	0	0.108	0.269
120b N 4th St, San Jose	1999	29	28	0.028	0.807
160 Cuesta Dr., Mountain View	1999	28	21	0.119	0.538
120b N 4th St, San Jose	2000	29	0	0.098	0.430



**TABLE 2**  
**TCE CONCENTRATIONS IN OUTDOOR AIR**  
**EPA AIR DATA**  
**BUILDING SPECIFIC WORK PLAN ADDENDUM: 811 EAST ARQUES**  
**SANTA CLARA COUNTY, CALIFORNIA**

Station Address	Year	Total Observations	Observations Non-Detected	Mean Concentration ( $\mu\text{g}/\text{m}^3$ )	Max Concentration ( $\mu\text{g}/\text{m}^3$ )
120b N 4th St, San Jose	2000	30	30	0.000	0.000
160 Cuesta Dr., Mountain View	2000	2	2	0.000	0.000
910 Ticonderoga Drive	2001	24	24	0.000	0.000
120b N 4th St, San Jose	2001	28	0	0.177	0.484
120b N 4th St, San Jose	2001	31	31	0.000	0.000
910 Ticonderoga Drive	2002	30	29	0.020	0.591
158b Jackson St	2002	6	0	0.170	0.269
158b Jackson St	2002	6	6	0.000	0.000
120b N 4th St, San Jose	2002	9	0	0.125	0.161
120b N 4th St, San Jose	2002	10	10	0.000	0.000
910 Ticonderoga Drive	2003	29	28	0.009	0.269
158b Jackson St	2003	31	0	0.101	0.376
158b Jackson St	2003	31	29	0.017	0.269
910 Ticonderoga Drive	2004	31	30	0.010	0.323
158b Jackson St	2004	30	0	0.070	0.215
158b Jackson St	2004	30	30	0.000	0.000
Whisman Park On Easy Street	2004	19	13	0.105	0.538
910 Ticonderoga Drive	2005	31	30	0.009	0.269
158b Jackson St	2005	31	0	0.062	0.161
158b Jackson St	2005	31	29	0.017	0.269
Whisman Park On Easy Street	2005	31	31	0.000	0.000
910 Ticonderoga Drive	2006	30	30	0.000	0.000
158b Jackson St	2006	30	0	0.056	0.108
158b Jackson St	2006	30	30	0.000	0.000
910 Ticonderoga Drive	2007	30	30	0.000	0.000
158b Jackson St	2007	30	0	0.061	0.161
158b Jackson St	2007	52	51	0.006	0.323
910 Ticonderoga Drive	2008	28	7	0.054	0.215
158b Jackson St	2008	31	0	0.054	0.054
158b Jackson St	2008	60	4	0.076	0.215
158b Jackson St	2009	31	0	0.068	0.269
158b Jackson St	2009	52	29	0.043	0.215
158b Jackson St	2010	30	0	0.054	0.054
158b Jackson St	2010	61	13	0.063	0.161
22601 Voss Ave	2010	20	4	0.073	0.161
158b Jackson St	2011	32	0	0.055	0.108
158b Jackson St	2011	60	34	0.032	0.161
22601 Voss Ave	2011	62	41	0.021	0.108
158b Jackson St	2012	29	0	0.057	0.134
158b Jackson St	2012	59	54	0.007	0.110
22601 Voss Ave	2012	61	57	0.007	0.202

**TABLE 2**  
**TCE CONCENTRATIONS IN OUTDOOR AIR**  
**EPA AIR DATA**  
**BUILDING SPECIFIC WORK PLAN ADDENDUM: 811 EAST ARQUES**  
**SANTA CLARA COUNTY, CALIFORNIA**

Station Address	Year	Total Observations	Observations Non-Detected	Mean Concentration ( $\mu\text{g}/\text{m}^3$ )	Max Concentration ( $\mu\text{g}/\text{m}^3$ )
158b Jackson St	2013	31	0	0.054	0.054
158b Jackson St	2013	60	54	0.010	0.172
22601 Voss Ave	2013	60	60	0.000	0.000
1007 Knox Ave	2014	13	13	0.000	0.000
158b Jackson St	2014	29	0	0.054	0.054
158b Jackson St	2014	60	55	0.005	0.091
1007 Knox Ave	2015	27	25	0.004	0.065
158b Jackson St	2015	30	0	0.054	0.054
158b Jackson St	2015	60	51	0.005	0.070
1007 Knox Ave	2016	31	29	0.004	0.075
158b Jackson St	2016	30	6	0.051	0.188
158b Jackson St	2016	60	59	0.000	0.022
1007 Knox Ave	2017	31	30	0.004	0.129
158b Jackson St	2017	27	26	0.010	0.269
158b Jackson St	2017	54	54	0.000	0.000
1007 Knox Ave	2018	26	26	0.000	0.000
158b Jackson St	2018	31	31	0.000	0.000
158b Jackson St	2018	44	44	0.000	0.000
1007 Knox Ave	2019	26	26	0.000	0.000
158b Jackson St	2019	30	29	0.009	0.269
158b Jackson St	2019	30	29	0.011	0.328
1007 Knox Ave	2020	28	28	0.000	0.000
158b Jackson St	2020	29	28	0.001	0.032
158b Jackson St	2020	9	9	0.000	0.000
1007 Knox Ave	2021	29	29	0.000	0.000
158b Jackson St	2021	22	22	0.000	0.000
158b Jackson St	2021	29	27	0.003	0.048

Notes:

Data Retrieved from: [www.epa.gov/outdoor-air-quality-data/monitor-values-report-hazardous-air-pollutants](http://www.epa.gov/outdoor-air-quality-data/monitor-values-report-hazardous-air-pollutants)  
on February 26, 2022.

**TABLE 3**  
**SAMPLING LOCATIONS AND ANALYSIS**  
**BUILDING SPECIFIC WORK PLAN ADDENDUM: 811 ARQUES**  
**SIGNETICS SITE, SUNNYVALE, CALIFORNIA**

Location	Location Type	Field Sample ID	Sample Purpose	Sample Method	Sample Analytical Method(s)	Sample Duration
Storage/Receiving Area Office	Vapor Pin	LOWES-VP-1	Regular	1-Liter Summa-passivated Canisters	USEPA Method TO-15, ASTM D1946	Grab
Sales floor (North)	Vapor Pin	LOWES-VP-2	Regular	1-Liter Summa-passivated Canisters	USEPA Method TO-15, ASTM D1946	Grab
Sales floor (Middle East)	Vapor Pin	LOWES-VP-3	Regular	1-Liter Summa-passivated Canisters	USEPA Method TO-15, ASTM D1946	Grab
Sales Floor (Middle West)	Vapor Pin	LOWES-VP-4	Regular	1-Liter Summa-passivated Canisters	USEPA Method TO-15, ASTM D1946	Grab
Sales Floor (South East)	Vapor Pin	LOWES-VP-5	Regular	1-Liter Summa-passivated Canisters	USEPA Method TO-15, ASTM D1946	Grab
Sales Floor (South West)	Vapor Pin	LOWES-VP-6	Regular	1-Liter Summa-passivated Canisters	USEPA Method TO-15, ASTM D1946	Grab
Office Space – Training Room	Vapor Pin	LOWES-VP-7	Regular	1-Liter Summa-passivated Canisters	USEPA Method TO-15, ASTM D1946	Grab
Water Fountains Outside Women's Restroom	Vapor Pin	LOWES-VP-8	Regular	1-Liter Summa-passivated Canisters	USEPA Method TO-15, ASTM D1946	Grab
Sewer Cleanout	Sewer Cleanout	LOWES-CO-1	Regular	1-Liter Summa-passivated Canisters	USEPA Method TO-15	Grab
To be determined in field	Vapor Pin	To be determined in field	Duplicate	1-Liter Summa-passivated Canisters	USEPA Method TO-15, ASTM D1946	Grab
To be determined in field	Not Applicable	To be determined in field	Field Blank	1-Liter Summa-passivated Canisters	USEPA Method TO-15, ASTM D1946	Grab

**TABLE 4**  
**SUB-SLAB SOIL GAS AND SEWER GAS EVALUATION CRITERIA**  
**BUILDING SPECIFIC WORK PLAN ADDENDUM: 811 EAST ARQUES**  
**SIGNETICS SITE, SUNNYVALE, CALIFORNIA**

	Chloroform	1,1-Dichloroethene (1,1-DCE)	1,1,2-Trichlorotrifluoroethane (FREON 113)	1,1-Dichloroethane (1,1-DCA)	cis-1,2-Dichloroethene	1,1,1-Trichloroethane (TCA)	Trichloroethene (TCE)	Tetrachloroethene (PCE)	trans-1,2-Dichloroethene	Vinyl Chloride
Indoor Air Screening Levels	53	70	22,000**	8	35**	1,000	3	2	350**	0.16
Sub-Slab Soil Gas and Sewer Gas Screening Levels	1,767	2,333	733,333	257	1,167	33,333	100	67	11,667	5
Eurofins TO-15 Reporting Levels TO-15 1-Liter Summa, as of May 2022	5.3	4.4	8.3	4.4	4.4	5.9	5.9	7.4	4.4	2.8
<b>Notes:</b>  All concentrations are reported in $\mu\text{g}/\text{m}^3$ (micrograms per cubic meter). Screening levels are intended for the purpose of initial evaluation of sub-slab concentrations, and are based on long-term criteria unless marked with **.  Subslab criteria were defined using indoor air screening levels with a 0.03 attenuation factor, per EPA guidance.  ** Screening levels based on short-term criteria (for compounds without applicable long-term criteria) as defined in Table 4 of Final Work Plan: Indoor Air/Vapor Intrusion Removal Site Evaluation and any Necessary Removal										

# Figures





Figure 1. Site Location  
Signetics Site  
Sunnyvale, California

0 0.2 0.4mi  
REV. 0 | 29 May 2020 | Final | DWN. BY: AT | CK'D BY: AE | AP'D BY: JWH



FILE NAME: Z:\LOCUS\TEC\PHILIPS SUNNYVALE\ITEMS\2022\815 STEWART\SM.0322\FIGURE 2 SIGNETICS 815 STEWART SITE PLAN ASM E284.0322.DWG



LEGEND:

----- 811 EAST ARQUES SITE BOUNDARY

REFERENCES:

1. LINEWORK FROM SANTA CLARA COUNTY INFORMATION SERVICES DEPARTMENT AND THE ASSESSORS OFFICE, COUNTYWIDE GIS MAP DATA AVAILABLE TO COUNTY DEPARTMENT, ITS PARTNERS AND THE PUBLIC AND THE CITY OF SUNNYVALE, CALIFORNIA GIS DATA, COPYRIGHT 2018.
2. SATELLITE IMAGERY U.S.G.S. EARTH EXPLORER™. THE ORTHOIMAGERY WAS EVALUATED BY THE U.S.G.S. AND MEETS THE NATIONAL MAP ACCURACY STANDARDS (95% CONFIDENCE). REPORT DATE JULY 24, 2015, COPYRIGHT 2018.

SITE PLAN – 811 EAST ARQUES  
SIGNETICS SITE  
SUNNYVALE, CALIFORNIA

PREPARED FOR  
PHILIPS  
SEMICONDUCTORS

△	07/20	ISSUED FOR STEWART DRIVE REPORT	AJK	NL	AEG
No.	DATE	ISSUE / REVISION	OWN. BY	CK'D BY	AP'D BY



0 200 400  
SCALE IN FEET

DRAWING NO.	27-006-E284
FIGURE 2	






Figure 3. Current Site Layout  
 811 East Arques, Sunnyvale, California  
 Drawings provided by Lowe's

REV	DATE	DESCRIPTION
01	08/12/2010	ISSUED FOR PERMIT
02	09/15/2010	REVISIONS
03	10/15/2010	REVISIONS
04	11/15/2010	REVISIONS
05	12/15/2010	REVISIONS
06	01/15/2011	REVISIONS
07	02/15/2011	REVISIONS
08	03/15/2011	REVISIONS
09	04/15/2011	REVISIONS
10	05/15/2011	REVISIONS
11	06/15/2011	REVISIONS
12	07/15/2011	REVISIONS
13	08/15/2011	REVISIONS
14	09/15/2011	REVISIONS
15	10/15/2011	REVISIONS
16	11/15/2011	REVISIONS
17	12/15/2011	REVISIONS
18	01/15/2012	REVISIONS
19	02/15/2012	REVISIONS
20	03/15/2012	REVISIONS
21	04/15/2012	REVISIONS
22	05/15/2012	REVISIONS
23	06/15/2012	REVISIONS
24	07/15/2012	REVISIONS
25	08/15/2012	REVISIONS
26	09/15/2012	REVISIONS
27	10/15/2012	REVISIONS
28	11/15/2012	REVISIONS
29	12/15/2012	REVISIONS
30	01/15/2013	REVISIONS
31	02/15/2013	REVISIONS
32	03/15/2013	REVISIONS
33	04/15/2013	REVISIONS
34	05/15/2013	REVISIONS
35	06/15/2013	REVISIONS
36	07/15/2013	REVISIONS
37	08/15/2013	REVISIONS
38	09/15/2013	REVISIONS
39	10/15/2013	REVISIONS
40	11/15/2013	REVISIONS
41	12/15/2013	REVISIONS
42	01/15/2014	REVISIONS
43	02/15/2014	REVISIONS
44	03/15/2014	REVISIONS
45	04/15/2014	REVISIONS
46	05/15/2014	REVISIONS
47	06/15/2014	REVISIONS
48	07/15/2014	REVISIONS
49	08/15/2014	REVISIONS
50	09/15/2014	REVISIONS
51	10/15/2014	REVISIONS
52	11/15/2014	REVISIONS
53	12/15/2014	REVISIONS
54	01/15/2015	REVISIONS
55	02/15/2015	REVISIONS
56	03/15/2015	REVISIONS
57	04/15/2015	REVISIONS
58	05/15/2015	REVISIONS
59	06/15/2015	REVISIONS
60	07/15/2015	REVISIONS
61	08/15/2015	REVISIONS
62	09/15/2015	REVISIONS
63	10/15/2015	REVISIONS
64	11/15/2015	REVISIONS
65	12/15/2015	REVISIONS
66	01/15/2016	REVISIONS
67	02/15/2016	REVISIONS
68	03/15/2016	REVISIONS
69	04/15/2016	REVISIONS
70	05/15/2016	REVISIONS
71	06/15/2016	REVISIONS
72	07/15/2016	REVISIONS
73	08/15/2016	REVISIONS
74	09/15/2016	REVISIONS
75	10/15/2016	REVISIONS
76	11/15/2016	REVISIONS
77	12/15/2016	REVISIONS
78	01/15/2017	REVISIONS
79	02/15/2017	REVISIONS
80	03/15/2017	REVISIONS
81	04/15/2017	REVISIONS
82	05/15/2017	REVISIONS
83	06/15/2017	REVISIONS
84	07/15/2017	REVISIONS
85	08/15/2017	REVISIONS
86	09/15/2017	REVISIONS
87	10/15/2017	REVISIONS
88	11/15/2017	REVISIONS
89	12/15/2017	REVISIONS
90	01/15/2018	REVISIONS
91	02/15/2018	REVISIONS
92	03/15/2018	REVISIONS
93	04/15/2018	REVISIONS
94	05/15/2018	REVISIONS
95	06/15/2018	REVISIONS
96	07/15/2018	REVISIONS
97	08/15/2018	REVISIONS
98	09/15/2018	REVISIONS
99	10/15/2018	REVISIONS
100	11/15/2018	REVISIONS
101	12/15/2018	REVISIONS
102	01/15/2019	REVISIONS
103	02/15/2019	REVISIONS
104	03/15/2019	REVISIONS
105	04/15/2019	REVISIONS
106	05/15/2019	REVISIONS
107	06/15/2019	REVISIONS
108	07/15/2019	REVISIONS
109	08/15/2019	REVISIONS
110	09/15/2019	REVISIONS
111	10/15/2019	REVISIONS
112	11/15/2019	REVISIONS
113	12/15/2019	REVISIONS
114	01/15/2020	REVISIONS
115	02/15/2020	REVISIONS
116	03/15/2020	REVISIONS
117	04/15/2020	REVISIONS
118	05/15/2020	REVISIONS
119	06/15/2020	REVISIONS
120	07/15/2020	REVISIONS
121	08/15/2020	REVISIONS
122	09/15/2020	REVISIONS
123	10/15/2020	REVISIONS
124	11/15/2020	REVISIONS
125	12/15/2020	REVISIONS
126	01/15/2021	REVISIONS
127	02/15/2021	REVISIONS
128	03/15/2021	REVISIONS
129	04/15/2021	REVISIONS
130	05/15/2021	REVISIONS
131	06/15/2021	REVISIONS
132	07/15/2021	REVISIONS
133	08/15/2021	REVISIONS
134	09/15/2021	REVISIONS
135	10/15/2021	REVISIONS
136	11/15/2021	REVISIONS
137	12/15/2021	REVISIONS
138	01/15/2022	REVISIONS
139	02/15/2022	REVISIONS
140	03/15/2022	REVISIONS
141	04/15/2022	REVISIONS
142	05/15/2022	REVISIONS
143	06/15/2022	REVISIONS
144	07/15/2022	REVISIONS
145	08/15/2022	REVISIONS
146	09/15/2022	REVISIONS
147	10/15/2022	REVISIONS
148	11/15/2022	REVISIONS
149	12/15/2022	REVISIONS
150	01/15/2023	REVISIONS
151	02/15/2023	REVISIONS
152	03/15/2023	REVISIONS
153	04/15/2023	REVISIONS
154	05/15/2023	REVISIONS
155	06/15/2023	REVISIONS
156	07/15/2023	REVISIONS
157	08/15/2023	REVISIONS
158	09/15/2023	REVISIONS
159	10/15/2023	REVISIONS
160	11/15/2023	REVISIONS
161	12/15/2023	REVISIONS
162	01/15/2024	REVISIONS
163	02/15/2024	REVISIONS
164	03/15/2024	REVISIONS
165	04/15/2024	REVISIONS
166	05/15/2024	REVISIONS
167	06/15/2024	REVISIONS
168	07/15/2024	REVISIONS
169	08/15/2024	REVISIONS
170	09/15/2024	REVISIONS
171	10/15/2024	REVISIONS
172	11/15/2024	REVISIONS
173	12/15/2024	REVISIONS
174	01/15/2025	REVISIONS
175	02/15/2025	REVISIONS
176	03/15/2025	REVISIONS
177	04/15/2025	REVISIONS
178	05/15/2025	REVISIONS
179	06/15/2025	REVISIONS
180	07/15/2025	REVISIONS
181	08/15/2025	REVISIONS
182	09/15/2025	REVISIONS
183	10/15/2025	REVISIONS
184	11/15/2025	REVISIONS
185	12/15/2025	REVISIONS
186	01/15/2026	REVISIONS
187	02/15/2026	REVISIONS
188	03/15/2026	REVISIONS
189	04/15/2026	REVISIONS
190	05/15/2026	REVISIONS
191	06/15/2026	REVISIONS
192	07/15/2026	REVISIONS
193	08/15/2026	REVISIONS
194	09/15/2026	REVISIONS
195	10/15/2026	REVISIONS
196	11/15/2026	REVISIONS
197	12/15/2026	REVISIONS
198	01/15/2027	REVISIONS
199	02/15/2027	REVISIONS
200	03/15/2027	REVISIONS
201	04/15/2027	REVISIONS
202	05/15/2027	REVISIONS
203	06/15/2027	REVISIONS
204	07/15/2027	REVISIONS
205	08/15/2027	REVISIONS
206	09/15/2027	REVISIONS
207	10/15/2027	REVISIONS
208	11/15/2027	REVISIONS
209	12/15/2027	REVISIONS
210	01/15/2028	REVISIONS
211	02/15/2028	REVISIONS
212	03/15/2028	REVISIONS
213	04/15/2028	REVISIONS
214	05/15/2028	REVISIONS
215	06/15/2028	REVISIONS
216	07/15/2028	REVISIONS
217	08/15/2028	REVISIONS
218	09/15/2028	REVISIONS
219	10/15/2028	REVISIONS
220	11/15/2028	REVISIONS
221	12/15/2028	REVISIONS
222	01/15/2029	REVISIONS
223	02/15/2029	REVISIONS
224	03/15/2029	REVISIONS
225	04/15/2029	REVISIONS
226	05/15/2029	REVISIONS
227	06/15/2029	REVISIONS
228	07/15/2029	REVISIONS
229	08/15/2029	REVISIONS
230	09/15/2029	REVISIONS
231	10/15/2029	REVISIONS
232	11/15/2029	REVISIONS
233	12/15/2029	REVISIONS
234	01/15/2030	REVISIONS
235	02/15/2030	REVISIONS
236	03/15/2030	REVISIONS
237	04/15/2030	REVISIONS
238	05/15/2030	REVISIONS
239	06/15/2030	REVISIONS
240	07/15/2030	REVISIONS
241	08/15/2030	REVISIONS
242	09/15/2030	REVISIONS
243	10/15/2030	REVISIONS
244	11/15/2030	REVISIONS
245	12/15/2030	REVISIONS
246	01/15/2031	REVISIONS
247	02/15/2031	REVISIONS
248	03/15/2031	REVISIONS
249	04/15/2031	REVISIONS
250	05/15/2031	REVISIONS
251	06/15/2031	REVISIONS
252	07/15/2031	REVISIONS
253	08/15/2031	REVISIONS
254	09/15/2031	REVISIONS
255	10/15/2031	REVISIONS
256	11/15/2031	REVISIONS
257	12/15/2031	REVISIONS
258	01/15/2032	REVISIONS
259	02/15/2032	REVISIONS
260	03/15/2032	REVISIONS
261	04/15/2032	REVISIONS
262	05/15/2032	REVISIONS
263	06/15/2032	REVISIONS
264	07/15/2032	REVISIONS
265	08/15/2032	REVISIONS
266	09/15/2032	REVISIONS
267	10/15/2032	REVISIONS
268	11/15/2032	REVISIONS
269	12/15/2032	REVISIONS
270	01/15/2033	REVISIONS
271	02/15/2033	REVISIONS
272	03/15/2033	REVISIONS
273	04/15/2033	REVISIONS
274	05/15/2033	REVISIONS
275	06/15/2033	REVISIONS
276	07/15/2033	REVISIONS
277	08/15/2033	REVISIONS
278	09/15/2033	REVISIONS
279	10/15/2033	REVISIONS
280	11/15/2033	REVISIONS
281	12/15/2033	REVISIONS
282	01/15/2034	REVISIONS
283	02/15/2034	REVISIONS
284	03/15/2034	REVISIONS
285	04/15/2034	REVISIONS
286	05/15/2034	REVISIONS
287	06/15/2034	REVISIONS
288	07/15/2034	REVISIONS
289	08/15/2034	REVISIONS
290	09/15/2034	REVISIONS
291	10/15/2034	REVISIONS
292	11/15/2034	REVISIONS
293	12/15/2034	



ED\_013761\_00000142-00045



**SENSOR WIRING NOTES:**





THE MECHANICAL CONTRACTOR SHALL WIRE THE INDOOR AIR (ZONE) SENSORS PROVIDED WITH THE H.V.A.C. UNITS ON THE BUILDING EXTERIOR. THE MECHANICAL CONTRACTOR SHALL CONNECT THESE SENSORS USING THE WIRING TO BE PROVIDED BY THE ELECTRICAL CONTRACTOR. THE MECHANICAL CONTRACTOR IS ALSO RESPONSIBLE FOR THE SENSORS CONNECTIONS AT THE ROOFTOP UNIT. ONCE THE SENSORS ARE INSTALLED AND WIRED, THE POWER SHOULD BE TURNED ON AND THE UNITS COMPLETELY CHECKED OUT. UNITS WILL OPERATE AT DEFAULT TEMPERATURES OF 71°F, HEAT AND 74°F, COOL.

THE SENSOR WIRING WILL BE RUN DOWN COLUMN FROM EACH RTU TO THE CORRESPONDING SENSOR IN 1/2\"/>

**2 COLUMN SENSOR MOUNTING**

SCALE 1/4\"/>

**Figure 5. RTU Layout**  
811 East Arques, Sunnyvale, California  
Drawings provided by Lowe's



**CURB NOTES**

1. GENERAL CONTRACTOR SHALL PURCHASE AND INSTALL CURB AND SHALL VERIFY THE EXACT LOCATION OF THE CURB PRIOR TO INSTALLATION. PRECISE LOCATION IS REQUIRED TO MAINTAIN COORDINATION WITH OTHER TRADES AS REQUIRED BY THESE DRAWINGS.
2. THE DIMENSIONS SHOWN ON THESE PLANS LOCATE THE CURB. THE LOCATION OF THE CURB ARE DESIGN TO OVERLAP PROJECT COORDINATION. THE LOCATION OF THE CURB EDGE OF THE CURB WILL VARY DEPENDING ON THE CURB MANUFACTURER SELECTED.
3. GENERAL CONTRACTOR SHALL CONTACT CURB SUPPLIER USING INFORMATION PROVIDED ON SHEET M-3 FOR DELIVERY AND SCHEDULING INFORMATION REQUIRED TO COORDINATE THIS PROJECT.
4. MECHANICAL CONTRACTOR SHALL BE RESPONSIBLE FOR WIRING AND REPLACING ALL CURBS, DECKS, AND EQUIPMENT OF OTHER TRADES THAT RESULT FROM ANY CURB NOT PROPERLY LOCATED ACCORDING TO THE REQUIREMENTS INDICATED BY THESE DRAWINGS.

**SHEET NOTES**

1. SEE GENERAL NOTES ON SHEET M-3.
2. COORDINATE INSTALLATION WITH ELECTRICAL SUB-CONTRACTOR (IF REQUIRED, THE PLUMBING SUB-CONTRACTOR IS RESPONSIBLE FOR INSTALLING GAS TYPING, SEE SHEET P-3. ALSO, IF REQUIRED, THE PLUMBING SUB-CONTRACTOR IS RESPONSIBLE FOR INSTALLING CONDENSATE PIPING, SEE SHEET P-3.)
3. COORDINATE INSTALLATION WITH THE GENERAL CONTRACTOR (SEE "CURB NOTES" ON THIS SHEET).

**REVISION**

NO.	DATE	DESCRIPTION
1	01/10	ISSUED FOR PERMIT
2	01/10	ISSUED FOR PERMIT
3	01/10	ISSUED FOR PERMIT
4	01/10	ISSUED FOR PERMIT
5	01/10	ISSUED FOR PERMIT
6	01/10	ISSUED FOR PERMIT
7	01/10	ISSUED FOR PERMIT
8	01/10	ISSUED FOR PERMIT
9	01/10	ISSUED FOR PERMIT
10	01/10	ISSUED FOR PERMIT

**PAGE INTERWORKS, P.A.**

**Nadel**

**LOWE'S**

**LOWE'S HAWAII**

1505 PARADISE AVE.,  
KAILUA, HI 96734  
TEL: 808-261-1000 FAX: 808-261-1001

**LOUIE'S**


**MECHANICAL EQUIPMENT PLAN**

**LOWE'S OF SUNNYVALE**

**M-1**




FIGURE 7  
BUILDING LAYOUT WITH PROPOSED SAMPLE LOCATIONS  
811 EAST ARQUES, SUNNYVALE, CALIFORNIA  
SIGNETICS SITE



NOTES  
1. Locations are approximate.

## SIGNETICS SITE




NOTE: ALL HORIZONTAL DRAINAGE PIPING SHALL  
HAVE A MIN. .125% SLOPE PER UPC 708.

# Appendix A:


## Relevant Groundwater Figures

FILE NAME: Z:\LOCUS\TEC\PHILIPS SUNNYVALE\GW\_OP\OPERABLE UNITS\DWGS - A\FIGURE 3, 8, 9, 10 & 24 UNITA.OOU BSM E284-2020.DWG





FILE NAME: Z:\LOCUS\TEC\PHILIPS SUNNYVALE\GW\_OPERABLE UNITS\DWGS - A\FIGURE 3, 8, 9, 10 & 24 UNITA.OOU BSM E284 - 2020.DWG







## **Appendix B:**

# **811 East Arques Commercial Indoor Air Survey**

# Non-Residential Survey Form

Date: 2/15/2022 Site: Philips - Arques EPA Building Number #: \_\_\_\_\_

Surveyor Name: Alan Tuan

Surveyor Title: \_\_\_\_\_

## PART 1: General Information

Business Name: Lowe's

Address: 811 E Arques  
Sunnyvale, CA

Tenant Information (if applicable)

Contact Name: Chad Dewayne / Gerald Sulicipan Interviewed: ☒ Yes ☐ No

Phone: 408-470-9190 / 408-332-4470 Email: Chad, M. Dewayne@store.loves.com

Owner/Landlord Information Consent Access ☒ Yes ☐ No Date: 10/13/2021

Name: Michael Aiken Interviewed: ☒ Yes ☐ No

Phone: 336-467-1573 Email: michael.aiken@loves.com

Building/Business Type (Check appropriate boxes)

☐ School/Day-Care ☒ Retail Store ☐ Office Space ☐ Warehouse ☐ Manufacturing

☒ Single level Office/Warehouse ☐ Multi-story ☐ Strip-mall ☐ Multi-tenant ☐ Warehouse

Other ☒ Hardware / Home improvement store

Building Occupancy

Typical Days/Hours of occupancy 2-3 hours in office area for meetings/breaks  
*Night shift! 8pm-5am steady shelves, Friday/ Sat night unoccupied, salary workers! 11 hours/day*

Typical Days/Hours of ventilation system operation 3 modes (customer, employee, unoccupied) *see Jason Peters email, Program Analyst,*

Name/Title of individual responsible for days/hours of operation Jason Peters / Facilities Asset

Building Characteristics

Year/Decade Built: 2005 Number of Stories: 1

Approximate Building Area (square feet): Total 135,000 sq ft First Floor \_\_\_\_\_

Is there an attached warehouse/shop space? \_\_\_\_\_ describe its use: \_\_\_\_\_

Foundation Type (Check appropriate boxes)

☒ Slab-on-Grade ☐ Slab-above-Grade (elevated/cap-slab on fill) ☐ Crawl Space ☐ Basement ☐ None

Describe \_\_\_\_\_

## Non-Residential Survey Form

Date: 2/15/2022 Site: Phillips - Arques EPA Building Number #: \_\_\_\_\_

### PART 2: Factors Impacting Indoor Air Quality and Sampling

#### Observations

What is the temperature relative to outside? slightly warmer.

What pathways to the subsurface were observed (e.g. utility conduits penetrating slab or interior wall/s, crawlspace openings or access points, floor drains)?

Floor drain in mens/women restroom, 1 in janitor closet. Utility conduit into slab in electrical room

Were windows/doors/roll-up doors kept open? side doors to garden area always open

Is there evidence of significant negative pressure? (e.g. using a facial tissue as a visual indicator or feeling for air movement with your hand, is air being drawn into the room/home: a) under the gap between the door and the floor when the door is closed, or b) through the doorway when the door is cracked open approximately 1/8<sup>th</sup> of an inch?) No

Do parts of the indoor environment appear stagnant? No

#### Building Construction

Building Construction Materials? ☒ Concrete ☐ Concrete Block ☐ Steel ☐ Wood ☐ Other \_\_\_\_\_

Does the building have an at-grade or below-grade garage? at-grade

Does the building have an attached mechanical room? electrical room

Is the building slab constructed with post-tension concrete [e.g. "post tension" indicated in a sign (stamped on the concrete floor near the edge of the main door or a plastic/paper sign on the wall) or cable tails evident in slab edges exposed on exterior walls, in stairwells, at balconies (circular, flush grout plugs 1.5" to 3" in diameter, 2' to 4' apart; or corroded cable tails)?

What are the ceiling heights? ~30'

## Non-Residential Survey Form

Date: 2/15/2022 Site: Philips-Arques EPA Building Number #: \_\_\_\_\_

### Pathway Analysis

Does the building have a basement or sub-surface structures that are/have: No

☐ Unfinished ☐ Exposed soil ☐ Damp or flooded ☐ Unsealed utility lines ☐ Other \_\_\_\_\_

Are there utilities that penetrate the slab that may be conduits for soil vapor? No, they are sealed,

Are these:

Connected to subsurface vaults? \_\_\_\_\_

Connected to utilities closer to potential VI sources? \_\_\_\_\_

In areas where pressure differential would cause air to flow through them? \_\_\_\_\_

Is there non-ventilated space in the building (maintenance / electrical / server rooms)? No

Is this space occupied? \_\_\_\_\_ At what frequency/duration? \_\_\_\_\_

Are there potential pathways in this space (e.g. utility conduits penetrating slab or interior wall/s, crawlspace openings or access points, floor drains)? \_\_\_\_\_

Are there significant heat sources or other systems that may generate a significant negative pressure near the floor/slab? \_\_\_\_\_

Are there elevators in the building? No

If the elevators are hydraulic plunger how deep does the piston penetrate below the slab? \_\_\_\_\_

Are there significant utilities penetrating the floor/slab? No

What is the condition of the foundation/slab? good, some cracks, mostly sealed,

Was the building constructed with a subslab system or barrier? Yes vapor (moisture) barrier.

Are there floor drains? Yes. Restrooms + Janitor closet, No drain in single occupancy bathroom,

If the foundation design specifications and/or as-built drawings are available attach.

**Other Information** (that may be of importance in understanding the indoor air quality)

See Jason Peters email regarding HVAC.

Check Hazardous Materials Business Plan, SDS Database most likely unhelpful.  
Can only search by name of product.

### Potential Sampling Locations

General notes on potential sample locations and type. Tentative sampling date(s) and preferred times.

Possibly 2 vapor pins in classrooms and 2 vapor pins on main floor.

On a separate page, draw/attach the general floor plan of the building and denote potential locations of sample collection.

# Non-Residential Survey Form

2/15/2022

Date: \_\_\_\_\_ Site: \_\_\_\_\_ EPA Building Number #: \_\_\_\_\_

## PART 4: Building Heating/Cooling/Ventilation Systems

### Systems Present

What types of systems are used for heating, cooling and ventilation? Check all that apply.

- ☐ Air Handler(s) ☒ Package Units ☐ Window/Wall systems ☐ Radiant heating (electric or water/steam)
- ☐ Evaporative Coolers ☐ Heat pump ☐ Built-up ☐ None Comments \_\_\_\_\_

Do the systems present provide make-up/fresh air? (Y/N) yes

Have the systems been evaluated for

ASHRAE Standard 62 compliance? yes

Fresh air should be supplied in all commercial/industrial/institutional settings. ASHRAE Standard 62, *Ventilation for Acceptable Indoor Air Quality*, has guidelines on how much air should be supplied. Meeting these requirements generally helps to mitigate VI impacts.

When was the system last tested and balanced? 2/14/2022 (attach report if available)

Is the ventilation system automated (building automation system)? yes

If yes is the data recorded or can it be recorded? \_\_\_\_\_

Note that the ventilation settings should be evaluated in the automation system and verified manually where possible.

### System operations

For each of the ventilation systems describe how is outdoor air supplied?

- Economizers: For RTU-3
  - Are economizers opening and closing properly? \_\_\_\_\_
  - minimum and maximum settings cfm or % 1656 cfm
- Manual adjustable outdoor air intakes No, Auto
  - Settings \_\_\_\_\_
- Fixed outdoor air intakes? \_\_\_\_\_
- Potential outdoor air intake not installed? \_\_\_\_\_
- Outdoor air intake not easily installed (e.g., split system, radiant heating) \_\_\_\_\_

How frequently are the ventilation systems serviced? \_\_\_\_\_

Are filters in good condition (i.e. not restricting airflow)? \_\_\_\_\_

Days and hours of operation for each ventilation system See Jason Peters email

Do any of the ventilation systems operate during nights and weekends? Y reduced settings? Y

Are the temperature / ventilation settings locked or routinely adjusted by the occupants? locked

What are the temperature settings? (note if seasonally variable) Days \_\_\_\_\_ Nights \_\_\_\_\_  
Weekends \_\_\_\_\_ see email

If there is an economizer, does the system control outdoor air supply using: (check all that apply)

## Non-Residential Survey Form

Date: 2/15/2022 Site: Phillips-Argos EPA Building Number #: \_\_\_\_\_

☐ Outdoor air temperature/enthalpy ☐ CO<sub>2</sub> concentration ☐ Other \_\_\_\_\_

Is there power exhaust? \_\_\_\_\_

Is the power exhaust setting dependent on ☐ economizer damper position ☐ Static pressure

Does the system use variable air volume distribution (VAV)? No

Can airflow be detected at indoor intakes and exhausts? \_\_\_\_\_

### Other Ventilation Issues impacting vapor intrusion potential.

Does the ventilation system have any underground components? No

Is ventilation being supplied or returned under a false floor above the building slab? No

Are ducting components routed through a basement, crawlspace, or utility vault area? No

Is a boiler or heater present in a basement or crawlspace? No describe \_\_\_\_\_

### Outdoor air intakes

Where are the outdoor air intakes located? Roof top

Are any outdoor air intakes physically obstructed? No

Are any intakes near sources of chemicals / sewer vents? No

Are there carbon filters present in the ventilation system? see e-mail

What make and model of filters are present and how often are they changed? \_\_\_\_\_

# Non-Residential Survey Form

Date: 2/15/2022 Site: \_\_\_\_\_ EPA Building Number #: \_\_\_\_\_

## Ventilation zones and settings

Zone/ Room	System Type	Supply Air Total cfm (range if VAV)	Supply Air % outdoor (range)	Ducted y/n	Return Air cfm	Ducted y/n

*see attached,*

## Non-Residential Survey Form

Date: 2/15/2022 Site: \_\_\_\_\_ EPA Building Number #: \_\_\_\_\_

Additional Notes:



## Alan Tuan

---

**From:** Peters, Jason <jason.peters@lowes.com>  
**Sent:** Tuesday, January 25, 2022 2:40 PM  
**To:** Alan Tuan; Aiken, Michael  
**Cc:** Dewayne, Chad; Africa Espina  
**Subject:** RE: [EXTERNAL] RE: STORE 2211 SUNNYVALE CA Locus Technologies Inspection


Alan,

I would not be able to meet onsite, unfortunately. Hopefully the explanations below are helpful. I can elaborate on any of these if needed.

There are three modes of operation for RTU's .

- Unoccupied
- Employee
- Customer

See below screenshot for setpoints and fan mode.



	Cust	Empl	Unocc
Cool	73.0 °F	73.0 °F	78.0 °F
Heat	68.0 °F	67.0 °F	65.0 °F
Fan	On	Auto	Auto

Warning: Changes may affect multiple units

Unoccupied – Burglar alarm set, no one in building.

Employee – Burglar alarm set, employees only in building.

Customer – Burglar alarm not set, customer hours.

Schedule for HVAC – Customer is a shift, based off of store hours. We change the setpoints -5/+5 minutes.

Schedule02 - Customer Schedule

Schedule List	
Schedule01	Store Hours Schedule
Schedule02	Customer Schedule
Schedule03	GC Lights Schedule
Schedule04	Site Lights Schedule
Schedule05	GC Hard Canopy Schedule
Schedule06	Exterior Security Schedule
Schedule07	Generator Schedule
Schedule08	Exception Schedule

Reference Schedule: Schedule01 (Store Hours Schedule)

	Sun	Mon	Tue	Wed	Thu	Fri	Sat
3:00 AM	Unoccupied	Unoccupied	Unoccupied	Unoccupied	Unoccupied	Unoccupied	Unoccupied
6:00 AM	Unoccupied	Occupied	Occupied	Occupied	Occupied	Occupied	Occupied
9:00 AM	Occupied	Occupied	Occupied	Occupied	Occupied	Occupied	Occupied
12:00 PM	Occupied	Occupied	Occupied	Occupied	Occupied	Occupied	Occupied
3:00 PM	Occupied	Occupied	Occupied	Occupied	Occupied	Occupied	Occupied
6:00 PM	Occupied	Occupied	Occupied	Occupied	Occupied	Occupied	Occupied
9:00 PM	Occupied	Occupied	Occupied	Occupied	Occupied	Occupied	Occupied
	-00h 05m +00h 05m	-00h 05m +00h 05m	-00h 05m +00h 05m	-00h 05m +00h 05m	-00h 05m +00h 05m	-00h 05m +00h 05m	-00h 05m +00h 05m

Reference	Shift	Event		
Start	05:35 PM	+00h 00m	05:35 PM	
Finish	05:35 PM	+00h 00m	05:35 PM	

☐ Default Schedule
☐ Alternate Schedules
☐ Special Events
☒ Summary


Jason Peters

Facilities Asset Program Analyst | Lowe's Companies Inc.  
C 704.960.9710

From: Alan Tuan &lt;tuana@locustec.com&gt;

Sent: Tuesday, January 25, 2022 1:23 PM

To: Peters, Jason &lt;jason.peters@lowes.com&gt;; Aiken, Michael &lt;michael.aiken@lowes.com&gt;

Cc: Dewayne, Chad &lt;Chad.M.Dewayne@store.lowes.com&gt;; Africa Espina &lt;guzuna@locustec.com&gt;

Subject: RE: [EXTERNAL] RE: STORE 2211 SUNNYVALE CA Locus Technologies Inspection

\*EXTERNAL SENDER\*

Hi Jason,

**Appendix C:**

**811 East Arques  
Hazardous Materials  
Business Plan**

**LOWE'S #2211 (CERSID: 10416037)****Facility Information**      **Submitted May 21, 2021**

Submitted on 5/21/2021 11:14:40 AM by *Maggie Ta* of Lowe's Home Centers, LLC (Mooresville, NC)  
Comments by Submitter: 2021 Annual Certification.

- Business Activities
- Business Owner/Operator Identification

**Hazardous Materials Inventory**      **Submitted May 21, 2021**

Submitted on 5/21/2021 11:14:40 AM by *Maggie Ta* of Lowe's Home Centers, LLC (Mooresville, NC)

- Hazardous Material Inventory (11)
- Site Map (Official Use Only)
  - *Annotated Facility Map #1 (Official Use Only)* (Adobe PDF, 1041KB)
  - *Annotated Site Map #2 (Official Use Only)* (Adobe PDF, 509KB)

**Emergency Response and Training Plans**      **Submitted May 21, 2021**

Submitted on 5/21/2021 11:14:40 AM by *Maggie Ta* of Lowe's Home Centers, LLC (Mooresville, NC)

- Emergency Response/Contingency Plan
  - *Emergency Response/Contingency Plan* (Adobe PDF, 212KB)
- Employee Training Plan
  - *Employee Training Plan* (Adobe PDF, 108KB)

**Aboveground Petroleum Storage Act**      **Submitted May 21, 2021**

Submitted on 5/21/2021 11:14:40 AM by *Maggie Ta* of Lowe's Home Centers, LLC (Mooresville, NC)

- Aboveground Petroleum Storage Act Documentation
  - *Stored At Facility LOWE'S #2211 CERSID (10416037)*
- APSA Facility Information

## Site Identification

## LOWE'S #2211

811 East Arques Avenue

Sunnyvale, CA 94085

County

Santa Clara

CERS ID

10416037

EPA ID Number

CAR000280123

## Submittal Status

Submitted on 5/21/2021 by *Maggie Ta* of Lowe's Home Centers, LLC (Mooresville, NC)

Comments by submitter: 2021 Annual Certification.

## Hazardous Materials

Does your facility have on site (for any purpose) at any one time, hazardous materials at or above 55 gallons for liquids, 500 pounds for solids, or 200 cubic feet for compressed gases (include liquids in ASTs and USTs); or is regulated under more restrictive inventory local reporting requirements (shown below if present); or the applicable Federal threshold quantity for an extremely hazardous substance specified in 40 CFR Part 355, Appendix A or B; or handle radiological materials in quantities for which an emergency plan is required pursuant to 10 CFR Parts 30, 40 or 70?

Yes

## Underground Storage Tank(s) (UST)

Does your facility own or operate underground storage tanks?

No

## Hazardous Waste

Is your facility a Hazardous Waste Generator?

Yes

Does your facility treat hazardous waste on-site?

No

Is your facility's treatment subject to financial assurance requirements (for Permit by Rule and Conditional Authorization)?

No

Does your facility consolidate hazardous waste generated at a remote site?

No

Does your facility need to report the closure/removal of a tank that was classified as hazardous waste and cleaned on-site?

No

Does your facility generate in any single calendar month 1,000 kilograms (kg) (2,200 pounds) or more of federal RCRA hazardous waste, or generate in any single calendar month greater than 1 kg (2.2 pounds) of RCRA acute hazardous waste; or generate more than 100 kg (220 pounds) of spill cleanup materials contaminated with RCRA acute hazardous waste.

No

Is your facility a Household Hazardous Waste (HHW) Collection site?

No

## Excluded and/or Exempted Materials

Does your facility recycle more than 100 kg/month of excluded or exempted recyclable materials (per HSC 25143.2)?

No

Does your facility own or operate ASTs above these thresholds? Store greater than 1,320 gallons of petroleum products (new or used) in aboveground tanks or containers.

Yes

Does your facility have Regulated Substances stored onsite in quantities greater than the threshold quantities established by the California Accidental Release prevention Program (CalARP)?

No

## Additional Information

No additional comments provided.

## Facility/Site

## LOWE'S #2211

811 East Arques Avenue  
Sunnyvale, CA 94085

CERS ID  
10416037

## Submittal Status

Submitted on 5/21/2021 by Maggie Ta of Lowe's Home Centers, LLC (Mooresville, NC)  
Comments by submitter: 2021 Annual Certification.

## Identification

Lowe's Home Centers, LLC

Operator Phone  
(408) 470-1680

Business Phone  
(888) 429-6281

Business Fax

Beginning Date

5/21/2021

Ending Date

5/31/2022

Dun &amp; Bradstreet

006997142

SIC Code

5211

Primary NAICS

## Facility/Site Mailing Address

2603 Main St., Suite 700  
Irvine, CA 92614

## Primary Emergency Contact

VARIES

Title

Manager on Duty

Business Phone

(408) 470-1680

24-Hour Phone

(888) 429-6281

Pager Number

## Owner

Lowe's Home Centers, LLC

(704) 758-6033

1000 Lowe's Blvd.

Mooresville, NC 28117

## Secondary Emergency Contact

INFO TRAC

Title

Lowe's HAZMAT Support Line (24/7/365)

Business Phone

(888) 429-6281

24-Hour Phone

(888) 429-6281

Pager Number

## Billing Contact

Rob Gass

(704) 758-6033

Robert.A.Gass@lowes.com

1000 Lowe's Blvd., Mail Code LPH28

Mooresville, NC 28117

## Environmental Contact

Laurie Litwin

(949) 244-6719

Laurie.M.Litwin@lowes.com

2603 Main St., Suite 700

Irvine, CA 92614

Name of Signer

Laurie Litwin

Signer Title

Regional Environmental Compliance Manager

Document Preparer

APTIM

Additional Information

## Locally-collected Fields

Some or all of the following fields may be required by your local regulator(s).

## Property Owner

Lowe's Home Centers, LLC

Phone

(704) 758-6033

Mailing Address

1000 Lowe's Blvd.

Mooresville, NC 28117

Assessor Parcel Number (APN)

205-27-012

Number of Employees

Facility ID

# Hazardous Materials And Wastes Inventory Matrix Report

CERS Business/Org.	<b>Lowe's Home Centers, LLC</b>	Chemical Location	CERS ID	<b>10416037</b>
Facility Name	<b>LOWE'S #2211</b>	<b>Back of Store in Hazardous Waste Accumulation Area (HWAC)</b>	Facility ID	
	811 East Arques Avenue, Sunnyvale 94085		Status	<b>Submitted</b> on 5/21/2021 11:14 AM

DOT Code/Fire Haz. Class	Common Name	Unit	Quantities			Annual Waste Amount	Federal Hazard Categories	Hazardous Components (For mixture only)		
			Max. Daily	Largest Cont.	Avg. Daily			Component Name	% Wt	EHS CAS No.
DOT: 3 - Flammable and Combustible Liquids	<b>Waste Aerosols</b>	<b>Gallons</b>	<b>55</b>	<b>55</b>	55	450	- Physical	Various Retail Aerosols	100 %	
Flammable Liquid, Class I-A,	CAS No.	State	Storage Container		Pressure	Waste Code	Flammable			
Flammable Liquid, Class I-B,	Map: 1	Liquid	Plastic/Non-metalic Drum		Ambient	331	- Physical Gas			
Flammable Liquid, Class I-C		Type			Temperature		Under Pressure			
		Waste	Days on Site: 365		Ambient		- Health			
							Carcinogenicity			
							- Health Acute			
							Toxicity			
							- Health			
							Reproductive			
							Toxicity			
							- Health Skin			
							Corrosion			
							Irritation			
							- Health			
							Respiratory Skin			
							Sensitization			
							- Health Serious			
							Eye Damage Eye			
							Irritation			
							- Health			
							Aspiration Hazard			
DOT: 8 - Corrosives (Liquids and Solids)	<b>Waste Corrosive Liquids (Acid)</b>	<b>Gallons</b>	<b>30</b>	<b>30</b>	30	100	- Physical	Various Acidic Products	100 %	
Corrosive	CAS No.	State	Storage Container		Pressure	Waste Code	Corrosive To			
	Map: 1	Liquid	Plastic/Non-metalic Drum		Ambient	791	Metal			
		Type			Temperature		- Health Acute			
		Waste	Days on Site: 365		Ambient		Toxicity			
							- Health Skin			
							Corrosion			
							Irritation			
							- Health Serious			
							Eye Damage Eye			
							Irritation			
DOT: 8 - Corrosives (Liquids and Solids)	<b>Waste Corrosive Liquids (Basic)</b>	<b>Gallons</b>	<b>60</b>	<b>30</b>	30	300	- Physical	Various Alkaline Products		
Corrosive	CAS No.	State	Storage Container		Pressure	Waste Code	Corrosive To			
	Map: 1	Liquid	Plastic/Non-metalic Drum		Ambient	122	Metal			
		Type			Temperature		- Health Acute			
		Waste	Days on Site: 365		Ambient		Toxicity			
							- Health Skin			
							Corrosion			
							Irritation			
							- Health Serious			
							Eye Damage Eye			
							Irritation			

## Hazardous Materials And Wastes Inventory Matrix Report

CERS Business/Org. <b>Lowe's Home Centers, LLC</b> Facility Name <b>LOWE'S #2211</b> 811 East Arques Avenue, Sunnyvale 94085	Chemical Location <b>Back of Store in Hazardous Waste Accumulation Area (HWAC)</b>	CERS ID <b>10416037</b> Facility ID Status <b>Submitted on 5/21/2021 11:14 AM</b>
--	---	---

DOT Code/Fire Haz. Class	Common Name	Unit	Quantities			Annual Waste Amount	Federal Hazard Categories	Hazardous Components (For mixture only)		
			Max. Daily	Largest Cont.	Avg. Daily			Component Name	% Wt	EHS CAS No.
DOT: 3 - Flammable and Combustible Liquids	<b>Waste Flammable Liquids</b>	<b>Gallons</b>	<b>55</b>	<b>55</b>	<b>55</b>	<b>800</b>	- Physical	Various Flammable Liquid	100 %	
	<u>CAS No</u>	<u>State</u>	<u>Storage Container</u>		<u>Pressure</u>	<u>Waste Code</u>	- Flammable	Products		
		<u>Liquid</u>	Plastic/Non-metalic Drum		<u>Ambient</u>		- Health			
	<u>Map: 1</u>	<u>Type</u>			<u>Temperature</u>	<b>331</b>	Carcinogenicity			
		<u>Waste</u>	Days on Site: 365		<u>Ambient</u>		- Health Acute			
							Toxicity			
							- Health			
							Respiratory Skin			
							Sensitization			
							- Health Serious			
							Eye Damage Eye			
							Irritation			
							- Health Specific			
							Target Organ			
							Toxicity			
							- Health Germ			
							Cell Mutagenicity			
DOT: 6.1 - Toxic Substances	<b>Waste Toxics</b>	<b>Gallons</b>	<b>55</b>	<b>55</b>	<b>55</b>	<b>600</b>	- Physical Hazard	Various Toxic Products	100 %	
Toxic	<u>CAS No</u>	<u>State</u>	<u>Storage Container</u>		<u>Pressure</u>	<u>Waste Code</u>	Not Otherwise			
		<u>Liquid</u>	Plastic/Non-metalic Drum		<u>Ambient</u>	<b>331</b>	Classified			
	<u>Map: 1</u>	<u>Type</u>			<u>Temperature</u>		- Health			
		<u>Waste</u>	Days on Site: 365		<u>Ambient</u>		Carcinogenicity			
							- Health Acute			
							Toxicity			
							- Health			
							Reproductive			
							Toxicity			
							- Health Skin			
							Corrosion			
							Irritation			
							- Health			
							Respiratory Skin			
							Sensitization			
							- Health Serious			
							Eye Damage Eye			
							Irritation			
							- Health Specific			
							Target Organ			
							Toxicity			



# Hazardous Materials And Wastes Inventory Matrix Report

CERS Business/Org. <b>Lowe's Home Centers, LLC</b> Facility Name <b>LOWE'S #2211</b> 811 East Arques Avenue, Sunnyvale 94085	Chemical Location <b>Back of Store in Hazardous Waste Accumulation Area (HWAC)</b>	CERS ID <b>10416037</b> Facility ID Status <b>Submitted on 5/21/2021 11:14 AM</b>
--	---	---

DOT Code/Fire Haz. Class	Common Name	Unit	Quantities			Annual Waste Amount	Federal Hazard Categories	Hazardous Components (For mixture only)		
			Max. Daily	Largest Cont.	Avg. Daily			Component Name	% Wt	EHS CAS No.
DOT: 3 - Flammable and Combustible Liquids	<b>Non-RCRA Hazardous Waste Liquid/Latex Paint/Class 9 Waste</b>	<b>Gallons</b>	<b>110</b>	<b>55</b>	<b>55</b>	<b>2000</b>	- Physical Hazard			
		State	Storage Container		Pressure	Waste Code	Not Otherwise			
		Liquid	Plastic/Non-metalic Drum		Ambient		Classified			
		CAS No			Temperature	331	- Health			
Combustible Liquid, Class III-B	Map: 1	Type			Ambient		Carcinogenicity			
		Waste	Days on Site: 365				- Health Acute			
							Toxicity			
							- Health			
DOT: 5.1 - Oxidizing Substances	<b>Waste Oxidizing Liquids</b>	<b>Gallons</b>	<b>55</b>	<b>55</b>	<b>55</b>	<b>10</b>	- Physical	Hydrogen Peroxide	60 %	✓ 7722-84-1
		State	Storage Container		Pressure	Waste Code	Flammable			
		Liquid	Plastic/Non-metalic Drum		Ambient	131	- Physical Organic			
		CAS No			Temperature		Peroxide			
Oxidizing, Class 1, Oxidizing, Class 2, Oxidizing, Class 3, Oxidizing, Class 4	Map: 1	Type			Ambient		- Health Acute			
		Waste	Days on Site: 365				Toxicity			
							- Health Skin			
							Corrosion			
							Irritation			
							- Health			
							Respiratory Skin			
							Sensitization			
							- Health Serious			
							Eye Damage Eye			
							Irritation			

# Hazardous Materials And Wastes Inventory Matrix Report

CERS Business/Org.	<b>Lowe's Home Centers, LLC</b>	Chemical Location	CERS ID	<b>10416037</b>
Facility Name	<b>LOWE'S #2211</b>	<b>Janitorial Closet</b>	Facility ID	
	811 East Arques Avenue, Sunnyvale 94085		Status	<b>Submitted</b> on 5/21/2021 11:14 AM

DOT Code/Fire Haz. Class	Common Name	Unit	Quantities			Annual Waste Amount	Federal Hazard Categories	Hazardous Components (For mixture only)		
			Max. Daily	Largest Cont.	Avg. Daily			Component Name	% Wt	EHS CAS No.
DOT: 3 - Flammable and Combustible Liquids	<b>Hand Sanitizer Gel</b>	<b>Gallons</b>	<b>148</b>	<b>1</b>	<b>148</b>		- Physical	Ethanol	73 %	64-17-5
	<u>CAS No.</u>	<u>State</u>	<u>Storage Container</u>		<u>Pressure</u>		Flammable			
		Liquid	Plastic Bottle or Jug		Ambient	<u>Waste Code</u>	- Physical Hazard	2-Propanol, 2-Methyl	0 %	75-65-0
		<u>Type</u>			<u>Temperature</u>		Not Otherwise	Methanol	0 %	67-56-1
		Mixture	Days on Site: 365		Ambient		Classified			
							- Health Serious			
							Eye Damage			
							Eye Irritation			

# Hazardous Materials And Wastes Inventory Matrix Report

CERS Business/Org. <b>Lowe's Home Centers, LLC</b>	Chemical Location	CERS ID <b>10416037</b>
Facility Name <b>LOWE'S #2211</b>	<b>Operational Equipment</b>	Facility ID
811 East Arques Avenue, Sunnyvale 94085		Status <b>Submitted on 5/21/2021 11:14 AM</b>

DOT Code/Fire Haz. Class	Common Name	Unit	Quantities			Annual Waste Amount	Federal Hazard Categories	Hazardous Components (For mixture only)		
			Max. Daily	Largest Cont.	Avg. Daily			Component Name	% Wt	EHS CAS No.
DOT: 2.1 - Flammable Gases	<b>Liquefied Petroleum Gas (lpg)</b>	<b>Gallons</b>	<b>1065</b>	<b>7.9</b>	<b>1065</b>		- Physical	Propane	85 %	74-98-6
Flammable Gas	CAS No	State	Storage Container		Pressure	Waste Code	Flammable	Propylene	15 %	115-07-1
	74-98-6	Liquid	Cylinder		> Ambient		- Physical Gas			
	Map: 1	Type			Temperature		Under Pressure			
		Mixture	Days on Site: 365		Ambient		- Health Acute			
							Toxicity			
							- Health Simple			
							Asphyxiant			

## Hazardous Materials And Wastes Inventory Matrix Report


CERS Business/Org.	<b>Lowe's Home Centers, LLC</b>	Chemical Location	CERS ID	<b>10416037</b>
Facility Name	<b>LOWE'S #2211</b>	<b>See Site Map</b>	Facility ID	
	811 East Arques Avenue, Sunnyvale 94085		Status	<b>Submitted</b> on 5/21/2021 11:14 AM

DOT Code/Fire Haz. Class	Common Name	Unit	Quantities			Annual Waste Amount	Federal Hazard Categories	Hazardous Components (For mixture only)		
			Max. Daily	Largest Cont.	Avg. Daily			Component Name	% Wt	EHS CAS No.
DOT: 3 - Flammable and Combustible Liquids	<b>Diesel Fuel</b>	<b>Gallons</b>	<b>1500</b>	<b>1500</b>	1500		- Physical	Diesel Mixture (varies by supplier)	100 %	68476-34-6
	CAS No.	State	Storage Container		Pressure	Waste Code	- Flammable			
Combustible Liquid, Class II	68476-34-6	Liquid	Aboveground Tank		Ambient		- Health			
	Map: 1	Type			Temperature		Carcinogenicity			
		Mixture	Days on Site: 365		Ambient		- Health Acute			
							Toxicity			
							- Health Skin			
							Corrosion			
							Irritation			
							- Health Specific			
							Target Organ			
							Toxicity			
							- Health			
							Aspiration Hazard			
DOT: 8 - Corrosives (Liquids and Solids)	<b>Lead Acid Batteries</b>	<b>Gallons</b>	<b>106</b>	<b>28</b>	106		- Physical	Sulfuric Acid	40 %	✓ 7664-93-9
	CAS No.	State	Storage Container		Pressure	Waste Code	Explosive			
Corrosive		Liquid	Other		Ambient		- Health			
	Map: 1	Type			Temperature		Carcinogenicity			
		Mixture	Days on Site: 365		Ambient		- Health Acute			
							Toxicity			
							- Health			
							Reproductive			
							Toxicity			
							- Health Skin			
							Corrosion			
							Irritation			
							- Health Serious			
							Eye Damage Eye			
							Irritation			
							- Health Specific			
							Target Organ			
							Toxicity			

FACILITY PLAN

SCALE: 1" = 50'-0"

Hazardous Waste  
Storage and 55-gallon  
POL Storage



KEY:

- EMERGENCY DIESEL GENERATOR, (CLASS II COMBUSTIBLE LIQUID)
- AEROSOLS LEVEL 2 & 3
- PAINTS/SOLVENTS/FLAMMABLE-COMBUSTIBLE LIQUIDS
- POOL CHEMICALS
- FERTILIZER
- CLEANING CHEMICALS
- GARDEN CHEMICALS
- ROOF COATING & MASONRY BAGGED GOODS


- GAS SHUTOFF
- ELECTRICAL SHUTOFF
- WATER SHUTOFF
- PERSONAL PROTECTIVE EQUIPMENT
- FIRST AID
- SPRINKLER SYSTEM VALVES
- FIRE HOSE VALVE

- spill containment & mitigation equipment
- Hazardous Waste Accumulation Area
- batteries
- propane
- emergency assembly area

FIRE EXTINGUISHER LEGEND

- 39 - 4A 60B:C FIRE EXTINGUISHER
- 3 - WATER TYPE FIRE EXTINGUISHER (GARDEN CENTER CANOPY AND RECEIVING AREA)

NOTE: AN AUTOMATIC FIRE SPRINKLER SYSTEM IS INSTALLED THROUGHOUT THE BUILDING



# CALIFORNIA ENVIRONMENTAL REPORTING SYSTEM (CERS) CONSOLIDATED EMERGENCY RESPONSE / CONTINGENCY PLAN

*Prior to completing this Plan, please refer to the INSTRUCTIONS FOR COMPLETING A CONSOLIDATED CONTINGENCY PLAN*

## A. FACILITY IDENTIFICATION AND OPERATIONS OVERVIEW

FACILITY ID #		1. CERS ID	A1. DATE OF PLAN PREPARATION/REVISION	A2.
		10416037	04/17/2017	
BUSINESS NAME (Same as Facility Name or DBA - Doing Business As)				3.
Lowe's #2211				
BUSINESS SITE ADDRESS				103.
811 East Arques Avenue				
BUSINESS SITE CITY		104.	ZIP CODE	105.
Sunnyvale		CA	94085	
TYPE OF BUSINESS (e.g., Painting Contractor)		A3.	INCIDENTAL OPERATIONS (e.g., Fleet Maintenance) A4.	
Retailer			NA	
THIS PLAN COVERS CHEMICAL SPILLS, FIRES, AND EARTHQUAKES INVOLVING: (Check all that apply)				A5.
<input checked="" type="checkbox"/> 1. HAZARDOUS MATERIALS; <input checked="" type="checkbox"/> 2. HAZARDOUS WASTES				

## B. INTERNAL RESPONSE

INTERNAL FACILITY EMERGENCY RESPONSE WILL OCCUR VIA: (Check all that apply)	B1.
<input checked="" type="checkbox"/> 1. CALLING PUBLIC EMERGENCY RESPONDERS (i.e., 9-1-1) <input checked="" type="checkbox"/> 2. CALLING HAZARDOUS WASTE CONTRACTOR <input checked="" type="checkbox"/> 3. ACTIVATING IN-HOUSE EMERGENCY RESPONSE TEAM	

## C. EMERGENCY COMMUNICATIONS, PHONE NUMBERS AND NOTIFICATIONS

Whenever there is an imminent or actual emergency situation such as an explosion, fire, or release, the Emergency Coordinator (or his/her designee when the Emergency Coordinator is on call) shall:

1. Activate internal facility alarms or communications systems, where applicable, to notify all facility personnel.
2. Notify appropriate local authorities (i.e., call 9-1-1).
3. Notify the California Office of Emergency Services at (800) 852-7550.

Before facility operations are resumed in areas of the facility affected by the incident, the emergency coordinator shall notify the California Department of Toxic Substances Control (DTSC), the local Unified Program Agency (UPA), and the local fire department's hazardous materials program that the facility is in compliance with requirements to:

1. Provide for proper storage and disposal of recovered waste, contaminated soil or surface water, or any other material that results from an explosion, fire, or release at the facility; and
2. Ensure that no material that is incompatible with the released material is transferred, stored, or disposed of in areas of the facility affected by the incident until cleanup procedures are completed.

INTERNAL FACILITY EMERGENCY COMMUNICATIONS OR ALARM NOTIFICATION WILL OCCUR VIA: (Check all that apply)		C1.
<input checked="" type="checkbox"/> 1. VERBAL WARNINGS; <input type="checkbox"/> 4. PAGERS;	<input checked="" type="checkbox"/> 2. PUBLIC ADDRESS OR INTERCOM SYSTEM; <input checked="" type="checkbox"/> 5. ALARM SYSTEM;	<input type="checkbox"/> 3. TELEPHONE; <input checked="" type="checkbox"/> 6. PORTABLE RADIO
NOTIFICATIONS TO NEIGHBORING FACILITIES THAT MAY BE AFFECTED BY AN OFF-SITE RELEASE WILL OCCUR BY: (Check all that apply)		C2.
<input checked="" type="checkbox"/> 1. VERBAL WARNINGS; <input type="checkbox"/> 4. PAGERS;	<input type="checkbox"/> 2. PUBLIC ADDRESS OR INTERCOM SYSTEM; <input type="checkbox"/> 5. ALARM SYSTEM;	<input checked="" type="checkbox"/> 3. TELEPHONE; <input type="checkbox"/> 6. PORTABLE RADIO
EMERGENCY RESPONSE PHONE NUMBERS:		
AMBULANCE, FIRE, POLICE AND CHP .....	9-1-1	
CALIFORNIA OFFICE OF EMERGENCY SERVICES (OES).....	(800) 852-7550	
NATIONAL RESPONSE CENTER (NRC) .....	(800) 424-8802	
POISON CONTROL CENTER .....	(800) 222-1222	
LOCAL UNIFIED PROGRAM AGENCY (UPA/CUPA) .....	(408) 730-7238	
OTHER (Specify):	C4.	C5.
		( )
NEAREST MEDICAL FACILITY / HOSPITAL NAME:	Kaiser Permanente Santa Clara Medical Center & Medical Offices	C6. (408) 851-5300
AGENCY NOTIFICATION PHONE NUMBERS:	CALIFORNIA DEPT. OF TOXIC SUBSTANCES CONTROL (DTSC) ....	(916) 255-3545
	REGIONAL WATER QUALITY CONTROL BOARD .....	(510) 622-2300
	U.S. ENVIRONMENTAL PROTECTION AGENCY (US EPA) .....	(800) 300-2193
	CALIFORNIA DEPT OF FISH AND GAME (DFG) .....	(916) 358-2900
	U.S. COAST GUARD .....	(202) 267-2180
	CAL/OSHA .....	(916) 263-2800
	STATE FIRE MARSHAL .....	(916) 445-8200
OTHER (Specify):	C9.	C10.
		( )
OTHER (Specify):	C11.	C12.
		( )

**D. EMERGENCY CONTAINMENT AND CLEANUP PROCEDURES**

SPILL PREVENTION, CONTAINMENT, AND CLEANUP PROCEDURES: (Check all boxes that apply to indicate your procedures for containing spills, releases, fires or explosions; and, preventing and mitigating associated harm to persons, property, and the environment.)

- ☒ 1. MONITOR FOR LEAKS, RUPTURES, PRESSURE BUILD-UP, ETC.; D1.
- ☐ 2. PROVIDE STRUCTURAL PHYSICAL BARRIERS (e.g., Portable spill containment walls);
- ☒ 3. PROVIDE ABSORBENT PHYSICAL BARRIERS (e.g., Pads, pigs, pillows);
- ☐ 4. COVER OR BLOCK FLOOR AND/ OR STORM DRAINS;
- ☐ 5. BUILT-IN BERM IN WORK / STORAGE AREA;
- ☒ 6. AUTOMATIC FIRE SUPPRESSION SYSTEM;
- ☒ 7. ELIMINATE SOURCES OF IGNITION FOR FLAMMABLE HAZARDS (e.g. Flammable liquids, Propane);
- ☒ 8. STOP PROCESSES AND/OR OPERATIONS;
- ☐ 9. AUTOMATIC / ELECTRONIC EQUIPMENT SHUT-OFF SYSTEM;
- ☒ 10. SHUT-OFF WATER, GAS, ELECTRICAL UTILITIES AS APPROPRIATE;
- ☒ 11. CALL 9-1-1 FOR PUBLIC EMERGENCY RESPONDER ASSISTANCE / MEDICAL AID;
- ☒ 12. NOTIFY AND EVACUATE PERSONS IN ALL THREATENED AREAS;
- ☒ 13. ACCOUNT FOR EVACUATED PERSONS IMMEDIATELY AFTER EVACUATION CALL;
- ☒ 14. PROVIDE PROTECTIVE EQUIPMENT FOR ON-SITE RESPONSE TEAM;
- ☒ 15. REMOVE OR ISOLATE CONTAINERS / AREA AS APPROPRIATE;
- ☒ 16. HIRE LICENSED HAZARDOUS WASTE CONTRACTOR;
- ☒ 17. USE ABSORBENT MATERIAL FOR SPILLS WITH SUBSEQUENT PROPER LABELING, STORAGE, AND HAZARDOUS WASTE DISPOSAL AS APPROPRIATE;
- ☐ 18. SUCTION USING SHOP VACUUM WITH SUBSEQUENT PROPER LABELING, STORAGE, AND HAZARDOUS WASTE DISPOSAL AS APPROPRIATE;
- ☐ 19. WASH / DECONTAMINATE EQUIPMENT W/ CONTAINMENT and DISPOSAL OF EFFLUENT / RINSATE AS HAZARDOUS WASTE;
- ☒ 20. PROVIDE SAFE TEMPORARY STORAGE OF EMERGENCY-GENERATED WASTES;
- ☒ 21. OTHER (Specify): ADDITIONAL INFORMATION RELATED TO SPILL MITIGATION PROCEDURES IS ATTACHED. D2.

**E. FACILITY EVACUATION**

THE FOLLOWING ALARM SIGNAL(S) WILL BE USED TO BEGIN EVACUATION OF THE FACILITY (CHECK ALL THAT APPLY): E1.

- ☐ 1. BELLS;
- ☒ 2. HORNS/SIRENS;
- ☒ 3. VERBAL (i.e., SHOUTING);
- ☒ 4. OTHER (Specify): PUBLIC EVACUATION WILL BE INITIATED VIA THE PUBLIC ADDRESS SYSTEM, SHOUTING, AND FIRE ALARM WHEN APPROPRIATE. E2.

THE FOLLOWING LOCATION(S) IS/ARE EVACUEE EMERGENCY ASSEMBLY AREA(S) (i.e., Front parking lot, specific street corner, etc.) E3.

Lowe's personnel will assist customers in locating the closest emergency exit. Once their department is clear of customers, the employees will proceed to the pre-determined evacuation and staging area to obtain further direction.

Note: The Emergency Coordinator must account for all on site employees and/or site visitors after evacuation.

☒ EVACUATION ROUTE MAP(S) POSTED AS REQUIRED E4.

Note: The map(s) must show primary and alternate evacuation routes, emergency exits, and primary and alternate staging areas, and must be prominently posted throughout the facility in locations where it will be visible to employees and visitors.

**F. ARRANGEMENTS FOR EMERGENCY SERVICES**

**Explanation of Requirement:** Advance arrangements with local fire and police departments, hospitals, and/or emergency services contractors should be made as appropriate for your facility. You may determine that such arrangements are not necessary.

ADVANCE ARRANGEMENTS FOR LOCAL EMERGENCY SERVICES (Check one of the following) F1.

- ☐ 1. HAVE BEEN DETERMINED NOT NECESSARY; or
- ☒ 2. THE FOLLOWING ARRANGEMENTS HAVE BEEN MADE (Specify): F2.
- SPECIALTY RESPONSE ARRANGEMENTS CAN BE MADE THROUGH LOWE'S HAZMAT SUPPORT LINE, AT 888-429-6281.



**G. EMERGENCY EQUIPMENT**

Check all boxes that apply to list emergency response equipment available at the facility and identify the location(s) where the equipment is kept and the equipment's capability, if applicable. [e.g., ☒ CHEMICAL PROTECTIVE GLOVES | Spill response kit | One time use, Oil & solvent resistant only.]

TYPE	EQUIPMENT AVAILABLE <sup>G1.</sup>	LOCATION	CAPABILITY (If applicable) <sup>G3.</sup>
<b>Safety and First Aid</b>	1. <input type="checkbox"/> CHEMICAL PROTECTIVE SUITS, APRONS, OR VESTS	NA <sup>G2.</sup>	NA <sup>G3.</sup>
	2. <input checked="" type="checkbox"/> CHEMICAL PROTECTIVE GLOVES	Various <sup>G4.</sup>	Spill Kits <sup>G5.</sup>
	3. <input type="checkbox"/> CHEMICAL PROTECTIVE BOOTS	NA <sup>G6.</sup>	NA <sup>G7.</sup>
	4. <input type="checkbox"/> SAFETY GLASSES / GOGGLES / SHIELDS	NA <sup>G8.</sup>	NA <sup>G9.</sup>
	5. <input type="checkbox"/> HARD HATS	NA <sup>G10.</sup>	NA <sup>G11.</sup>
	6. <input type="checkbox"/> CARTRIDGE RESPIRATORS	NA <sup>G12.</sup>	NA <sup>G13.</sup>
	7. <input type="checkbox"/> SELF-CONTAINED BREATHING APPARATUS (SCBA)	NA <sup>G14.</sup>	NA <sup>G15.</sup>
	8. <input checked="" type="checkbox"/> FIRST AID KITS / STATIONS	Various <sup>G16.</sup>	Various locations throughout facility <sup>G17.</sup>
	9. <input type="checkbox"/> PLUMBED EYEWASH FOUNTAIN / SHOWER	NA <sup>G18.</sup>	NA <sup>G19.</sup>
	10. <input checked="" type="checkbox"/> PORTABLE EYEWASH KITS	Various <sup>G20.</sup>	Available <sup>G21.</sup>
	11. <input type="checkbox"/> OTHER	NA <sup>G22.</sup>	NA <sup>G23.</sup>
	12. <input type="checkbox"/> OTHER	NA <sup>G24.</sup>	NA <sup>G25.</sup>
<b>Fire Fighting</b>	13. <input checked="" type="checkbox"/> PORTABLE FIRE EXTINGUISHERS	Various <sup>G26.</sup>	Various locations throughout facility <sup>G27.</sup>
	14. <input checked="" type="checkbox"/> FIXED FIRE SYSTEMS / SPRINKLERS / FIRE HOSES	Various <sup>G28.</sup>	Fully monitored sprinkler system <sup>G29.</sup>
	15. <input checked="" type="checkbox"/> FIRE ALARM BOXES OR STATIONS	Front of Store <sup>G30.</sup>	Manual Fire Alarm Pull Station <sup>G31.</sup>
	16. <input type="checkbox"/> OTHER	NA <sup>G32.</sup>	NA <sup>G33.</sup>
<b>Spill Control and Clean-Up</b>	17. <input checked="" type="checkbox"/> ALL-IN-ONE SPILL KIT	Various <sup>G34.</sup>	Various locations throughout facility <sup>G35.</sup>
	18. <input checked="" type="checkbox"/> ABSORBENT MATERIAL	Various <sup>G36.</sup>	Various locations throughout facility <sup>G37.</sup>
	19. <input checked="" type="checkbox"/> CONTAINER FOR USED ABSORBENT	Various <sup>G38.</sup>	Back of Store, Waste Storage Area <sup>G39.</sup>
	20. <input type="checkbox"/> BERMING / DIKING EQUIPMENT	NA <sup>G40.</sup>	NA <sup>G41.</sup>
	21. <input checked="" type="checkbox"/> BROOM	Various <sup>G42.</sup>	Various locations throughout facility <sup>G43.</sup>
	22. <input type="checkbox"/> SHOVEL	NA <sup>G44.</sup>	NA <sup>G45.</sup>
	23. <input type="checkbox"/> SHOP VAC	NA <sup>G46.</sup>	NA <sup>G47.</sup>
	24. <input type="checkbox"/> EXHAUST HOOD	NA <sup>G48.</sup>	NA <sup>G49.</sup>
	25. <input type="checkbox"/> EMERGENCY SUMP / HOLDING TANK	NA <sup>G50.</sup>	NA <sup>G51.</sup>
	26. <input type="checkbox"/> CHEMICAL NEUTRALIZERS	NA <sup>G52.</sup>	NA <sup>G53.</sup>
	27. <input type="checkbox"/> GAS CYLINDER LEAK REPAIR KIT	NA <sup>G54.</sup>	NA <sup>G55.</sup>
	28. <input type="checkbox"/> SPILL OVERPACK DRUMS	NA <sup>G56.</sup>	NA <sup>G57.</sup>
	29. <input type="checkbox"/> OTHER	NA <sup>G58.</sup>	NA <sup>G59.</sup>
<b>Communications and Alarm Systems</b>	30. <input checked="" type="checkbox"/> TELEPHONES (Includes cellular)	Various <sup>G60.</sup>	Various locations throughout facility <sup>G61.</sup>
	31. <input checked="" type="checkbox"/> INTERCOM / PA SYSTEM	Various <sup>G62.</sup>	Various locations throughout facility <sup>G63.</sup>
	32. <input checked="" type="checkbox"/> PORTABLE RADIOS	Various <sup>G64.</sup>	Various locations throughout facility <sup>G65.</sup>
	33. <input checked="" type="checkbox"/> AUTOMATIC ALARM CHEMICAL MONITORING EQUIPMENT	Various <sup>G66.</sup>	Various locations throughout facility <sup>G67.</sup>
<b>Other</b>	34. <input checked="" type="checkbox"/> OTHER	Interstitial Monitoring (If Facility has a AST) <sup>G68.</sup>	Tank leak detection Systems Audible and electronic Alarms <sup>G69.</sup>

## H. EARTHQUAKE VULNERABILITY

Identify areas of the facility that are vulnerable to hazardous materials releases / spills due to earthquake-related motion. These areas require immediate isolation and inspection.

VULNERABLE AREAS: (Check all that apply) <input checked="" type="checkbox"/> 1. HAZARDOUS MATERIALS / WASTE STORAGE AREA <input type="checkbox"/> 2. PROCESS LINES / PIPING <input type="checkbox"/> 3. LABORATORY <input type="checkbox"/> 4. WASTE TREATMENT AREA	H1.	LOCATIONS (e.g., shop, outdoor shed, forensic lab) Hazardous Waste Accumulation & Generator/Tank Area    	H2. H3. H4. H5.
---	-----	--	--------------------------

Identify mechanical systems vulnerable to releases / spills due to earthquake-related motion. These systems require immediate isolation and inspection.

VULNERABLE SYSTEMS: (Check all that apply) <input checked="" type="checkbox"/> 1. SHELVES, CABINETS AND RACKS <input checked="" type="checkbox"/> 2. TANKS (EMERGENCY SHUTOFF) <input checked="" type="checkbox"/> 3. PORTABLE GAS CYLINDERS <input checked="" type="checkbox"/> 4. EMERGENCY SHUTOFF AND/OR UTILITY VALVES <input checked="" type="checkbox"/> 5. SPRINKLER SYSTEMS <input type="checkbox"/> 6. STATIONARY PRESSURIZED CONTAINERS (e.g., Propane dispensing tank)	H6.	LOCATIONS Throughout store Generator/Tank See Map for location of propane cylinders See Map Throughout the facility	H7. H8. H9. H10. H11. H12.
--	-----	--	---

## I. EMPLOYEE TRAINING

**Explanation of Requirement:** Employee training is required for all employees handling hazardous materials and hazardous wastes in day-to-day or clean-up operations including volunteers and/or contractors. Training must be:

- Provided within 6 months for new hires;
- Amended as necessary prior to change in process or work assignment;
- Given upon modification to the Emergency Response / Contingency Plan, and updated/refreshed annually for all employees.

Required content includes all of the following:

- |   |  |
|---|--|
| <ul style="list-style-type: none"> <li>• Material Safety Data Sheets;</li> <li>• Hazard communication related to health and safety;</li> <li>• Methods for safe handling of hazardous substances;</li> <li>• Fire hazards of materials / processes;</li> <li>• Conditions likely to worsen emergencies;</li> <li>• Coordination of emergency response;</li> <li>• Notification procedures;</li> <li>• Applicable laws and regulations;</li> </ul> | <ul style="list-style-type: none"> <li>• Communication and alarm systems;</li> <li>• Personal protective equipment;</li> <li>• Use of emergency response equipment (e.g. Fire extinguishers, respirators, etc.);</li> <li>• Decontamination procedures;</li> <li>• Evacuation procedures;</li> <li>• Control and containment procedures;</li> <li>• UST monitoring system equipment and procedures (if applicable).</li> </ul> |
|---|--|

INDICATE HOW EMPLOYEE TRAINING PROGRAM IS ADMINISTERED (Check all that apply)

- |   |  |
|---|--|
| <input type="checkbox"/> 1. FORMAL CLASSROOM;<br><input type="checkbox"/> 4. STUDY GUIDES / MANUALS (Specify): _____                    | <input type="checkbox"/> 2. VIDEOS;<br><input checked="" type="checkbox"/> 5. OTHER (Specify): <u>Training Materials through the Lowe's Learning Center (LLC).</u> |
| <input type="checkbox"/> 3. SAFETY / TAILGATE MEETINGS;<br><input type="checkbox"/> 6. NOT APPLICABLE BECAUSE FACILITY HAS NO EMPLOYEES |  |

**Large Quantity Generator (LQG) Training Records:** Large quantity hazardous waste generators (i.e., who generate more than 270 gallons/1,000 kilograms of hazardous waste per month) must retain written documentation of employee hazardous waste management training sessions which includes:

- A written outline/agenda of the type and amount of both introductory and continuing training that will be given to persons filling each job position having responsibility for the management of hazardous waste (e.g., labeling, manifesting, compliance with accumulation time limits, etc.).
- The name, job title, and date of training for each hazardous waste management training session given to an employee filling such a job position; and
- A written job description for each of the above job positions that describes job duties and the skills, education, or other qualifications required of personnel assigned to the position.
- Current employee training records must be retained until closure of the facility.
- Former employee training records must be retained at least three years after termination of employment.

## J. LIST OF ATTACHMENTS

(Check one of the following)

- |   |                |
|---|----------------|
| <input type="checkbox"/> 1. NO ATTACHMENTS ARE REQUIRED; or<br><input checked="" type="checkbox"/> 2. THE FOLLOWING DOCUMENTS ARE ATTACHED: | J1.<br><br>J2. |
|---|----------------|
1. Spill Cleanup Procedures
  2. Additional training plan information
  3. Sample HW Inspection Log

## K. SIGNATURE / CERTIFICATION

**Certification:** Based on my inquiry of those individuals responsible for obtaining the information, I certify under penalty of law that I have personally examined and am familiar with the information submitted and believe the information is true, accurate, and complete, and that a copy is available on site.

SIGNATURE OF OWNER/OPERATOR <i>Laurie Litwin</i>	K1.	DATE SIGNED 04/17/2017	K2.
NAME OF SIGNER (print) Laurie Litwin	K2.	TITLE OF SIGNER Regional Environmental Compliance Manager	K3.

# Supplemental Emergency Response/Contingency Plan Information

## Employee Training Plan (Hazardous Materials Business Plan Module)

Authority Cited: HSC, Section 25504(c); Title 22, Div. 4.5, Ch. 12, Art. 3 CCR

All facilities that handle hazardous materials must have a written employee training plan. This plan is a required module of the Hazardous Materials Business Plan (HMBP). A blank plan has been provided below for you to complete and submit if you do not already have such a plan. If you already have a brief written description of your training program that addresses all subjects covered below, you are not required to complete the blank plan, below, but you must include a copy of your existing document as part of your HMBP.

Check all boxes that apply. [Note: Items marked with an asterisk (\*) are required.]:

**1. Personnel** are trained in the following procedures:

<input checked="" type="checkbox"/>	Internal alarm/notification *
<input checked="" type="checkbox"/>	Evacuation/re-entry procedures & assembly point locations*
<input type="checkbox"/>	Emergency incident reporting
<input type="checkbox"/>	External emergency response organization notification
<input checked="" type="checkbox"/>	Location(s) and contents of Emergency Response/Contingency Plan
<input checked="" type="checkbox"/>	Facility evacuation drills, that are conducted at least ( <i>specify</i> ) Annually

### Lowe's Training Procedures:

Training shall be provided for all new employees, and annually, including refresher courses, for all employees.

Facility personnel are trained as follows:

- Familiarity with all plans and procedures specified in the Contingency Plan.
- Methods for safe handling of hazardous materials.
- Safety procedures in the event of a release or threatened release of a hazardous material.
- Use of Emergency Response Equipment and supplies under the control of the business.
- Procedures for coordination with local Emergency Responder organizations.
- Employees are trained on how to read a Material Safety Data Sheet (MSDS) and how to obtain a copy of an MSDS for review.

Training for workers handling hazardous waste:

- Facility personnel will successfully complete training within six months after the date of their employment or assignment to the store or to a new position at the store.
- Employees will not handle hazardous wastes without supervision until trained.

Training procedures for new employees is through the Lowe's Learning Center (LLC) at the facility, and include on the job training. Training procedures are refreshed annually for hazardous materials storage, labeling, record keeping, and handling requirements; the Hazardous Materials Business Plan (HMBP) is reviewed by applicable new employees, to all applicable employees on an annual basis, and is available for all associates review in the Manager's office and on Lowe's employee intranet site. Material Safety Data Sheets are available on Lowe's intranet site for review or printed out for onsite reference. The Human Resources Manager tracks training records and manifests, respectfully. Training records and manifests are available for review upon request with the store manager. All employees are required to participate in the Emergency Preparedness Program to assure evacuation routes and meeting place are known in the event of an emergency. The Automatic Fire Sprinkler System is checked by a licensed vendor annually.

### Personnel/Capabilities:

A. Are there any specially trained hazardous materials emergency response personnel at your business?  
Yes \_\_\_\_\_ No X \_\_\_\_\_ Number Trained \_\_\_\_\_

B. Do you have decontamination capabilities for victims of exposure to hazardous materials at your business? Yes \_\_\_\_\_ No X \_\_\_\_\_ Type of Decon \_\_\_\_\_

C. Do you have personnel that will provide site security at your business during and after a hazardous materials incident? Yes \_\_\_\_\_ No X \_\_\_\_\_ Titles of Personnel \_\_\_\_\_

## 2. Chemical Handlers are additionally trained in the following:

- |  |
|--|
| <input checked="" type="checkbox"/> Safe methods for handling and storage of hazardous materials *   |
| <input checked="" type="checkbox"/> Location(s) and proper use of fire and spill control equipment   |
| <input checked="" type="checkbox"/> Spill procedures/emergency procedures  |
| <input checked="" type="checkbox"/> Proper use of personal protective equipment *  |
| <input checked="" type="checkbox"/> Specific hazard(s) of each chemical to which they may be exposed, including routes of exposure ( <i>i.e. inhalation, ingestion, absorption</i> ) *   |
| <input checked="" type="checkbox"/> <b>Hazardous Waste Handlers/Managers</b> are trained in all aspects of hazardous waste management specific to their job duties ( <i>e.g. container accumulation time requirements, labeling requirements, storage area inspection requirements, manifesting requirements, etc.</i> ) * |

### Prevention:

Lowe's maintains hazardous chemicals in pre-packaged consumer products merchandised for retail sale. Products merchandised are stocked in such a manner as to preclude accidental damage, and to prevent spills or accidental mixtures. For example: 1) hazardous products maintained in small containers are kept in original boxes cut with lips or guards to prevent products from falling from shelves; 2) products maintained in overstock are kept in original unopened boxes, and wherever possible, boxes are secured with shrink wrapping material; and 3) incompatible products are separated by distance or partition to preclude mixture.

(If applicable) - Lowe's maintains an emergency generator for backup emergency power. The emergency generator contains diesel fuel, which is combustible. A low level detector to monitor the liquid level in the diesel fuel tank helps notify if any leaks in the tank were to occur and a trouble signal would be given to notify the proper authority.

Forklifts are also regularly used within the Lowe's stores. Forklift batteries contain hazardous materials and should be treated with care. When the batteries need charging, the forklifts are driven to a designated location where they are connected to a charging circuit until fully charged. The batteries are regularly checked for damage and/or leaks and would be treated appropriately.

Hazardous wastes are labeled and secured in the hazardous waste accumulation area. Universal wastes are labeled and secured in the Receiving Area in the back of the store.

### Mitigation:

In the case of a spill in the hazmat waste cage area, the spill would be contained with absorbent materials if it is not too large, and the manager notified for further guidance. For larger spills, InfoTrac will be contacted at 888-429-6281 to provide proper direction for contacting clean-up contractors, notifying the corporate offices and proper authorities.

Once a Lowe's employee discovers or is informed of a release, they should take the following steps:

- 1) Immediately evacuate the affected area of all customers and non-essential personnel
- 2) Notify a manager or assistant
- 3) Obtain a spill clean-up kit
- 4) Contact InfoTrac/HAZMAT Support Line for specific clean-up instructions.

If the spill is greater than 5 gallons or exceeds CERCLA reportable quantity, the following procedures apply:

- 1) Evacuate the area
- 2) Notify appropriate local authorities (e.g., Fire Department/911)
- 3) Notify the Hazmat Support Line (InfoTrac) at 888-429-6281 to report the spill
  - The Lowe's Corporate Hazmat Compliance Team, in conjunction with InfoTrac, will review the incident and determine the necessary response action.
  - If necessary, the Lowe's Corporate Hazmat Compliance Team will notify the appropriate regulatory authorities (e.g., Cal EMA and the CUPA) to ensure the facility meets all necessary pre- and post- incident reporting requirements.
- 4) Immediate containment of spill if possible, and
- 5) Notification of Corporate personnel.

### Abatement:

If the spill is small and easily contained, Lowe's trained personnel will obtain a spill clean-up kit (containing PPE,

absorbent, bucket, broom, dustpan, labeling materials, mild detergent) and contact InfoTrac for specific clean-up instructions. For large spills, after evacuation of the area, the fire department, InfoTrac and Corporate personnel are contacted and notified. In the unlikely event that a spill would require a prolonged clean-up procedure, Lowe's would contact an emergency response contractor. These contractors will utilize properly trained personnel to clean-up and remove hazardous waste at the facility. In the event of an emergency, the fire department will be contacted to respond to and mitigate the emergency.

## Record Keeping (Hazardous Materials Business Plan Module)

All facilities that handle hazardous materials must maintain records associated with their management. A summary of your recordkeeping procedures is a required module of the Hazardous Materials Business Plan (HMBP). A blank summary has been provided below for you to complete and submit if you do not already have such a document. **If you already have a brief written description of your hazardous materials recordkeeping systems that addresses all subjects covered below, you are not required to complete this page, but you must include a copy of your existing document as part of your HMBP.**

Check all boxes that apply. The following records are maintained at the facility. *[Note: Items marked with an asterisk (\*) are required.]*:

<input checked="" type="checkbox"/>	Current employees' training records <i>(to be retained until closure of the facility)</i> *
<input checked="" type="checkbox"/>	Former employees' training records <i>(to be retained at least three years after termination of employment)</i> *
<input checked="" type="checkbox"/>	Training Program(s) <i>(i.e. written description of introductory and continuing training)</i> *
<input checked="" type="checkbox"/>	Current copy of this Emergency Response/Contingency Plan *
<input type="checkbox"/>	Record of recordable/reportable hazardous material/waste releases *
<input checked="" type="checkbox"/>	Record of hazardous material/waste storage area inspections *
<input type="checkbox"/>	Record of hazardous waste tank daily inspections *
<input type="checkbox"/>	Description and documentation of facility emergency response drills

*Note: The above list of records does not necessarily identify every type of record required to be maintained by the facility.*

**A copy of the Inspection Check Sheet(s) or Log(s) used in conjunction with required routine self-inspections of your facility must be submitted with your HMBP.** *(Exception: Available from your local agency is a Hazardous Materials/Waste Storage Area Inspection Form that you may use if you do not already have your own form. If you use the example provided, you do not need to attach a copy.)*

Check the appropriate box:

<input type="checkbox"/>	We will use the Unidocs "Hazardous Materials/Waste Storage Area Inspection Form" to document inspections.
<input checked="" type="checkbox"/>	We will use our own documents to record inspections. <b><i>(A blank copy of each document used must be attached to this HMBP.)</i></b>

**Task Completion Surveys -  
Conduct Hazmat Program  
Inspection**

*	Is the Hazmat Cage kept locked with a Best Lock Core #6X?	Yes/No
*	Is the Hazmat Cage clean and orderly with adequate space to access the drums and view the drum labels?	Yes/No
*	Is the Hazmat Storage Area Sign (Archway item on Spend Management #30734B) and "No Smoking Sign" posted?	Yes/No
*	Is there a charged and accessible ABC Fire extinguisher within 75 feet of the cage, but not mounted on the cage?	Yes/No
*	Are all of the waste storage containers properly labeled and secured (lid in place and secure)?	Yes/No
*	Is all waste product properly segregated in bags, labeled and stored in the appropriate drums in the hazmat cage? Verify the Inventory Logs are current, accurate and complete for each drum.	Yes/No
*	Are all waste storage drums in good condition (i.e. free of rust, holes, leaks, or other visible damage)? Report any concerns to the Lowe's Hazmat Support Line at 1-888-429-6281.	Yes/No
*	Is the area around the Trash Compactor on the exterior of the building free from signs of leaking hydraulic oil? "If No" and oil is present on the ground, contact the Lowe's Hazmat Support Line at 1-888-429-6281. Conduct a visual inspection only.	Yes/No
*	Is the receiving/RTM area free of any product waiting to be classified for hazmat disposal? Note: All classifications should occur within two hours of waste designation.	Yes/No
*	Are the waste 4', 8' and CFL fluorescent bulb disposal boxes properly labeled as Universal Waste Bulbs with the accumulation start date, lids closed, and full boxes sealed?	Yes/No
*	Is the compactor door closed and locked and the Hazmat Notification sign (Non-California #G237643, CA Stores #G237645 in Spend Management) posted on the compactor door inside the Receiving Area?	Yes/No

**Task Completion Surveys -  
Conduct Emergency Power  
Generator Above-Ground  
Tank Inspection**

*	Is the area around the generator, transformer and piping free of any active leaks and evidence of any spills that were not cleaned up? If no, call the Hazmat Support Line at 1-888-429-6281.	Yes/No
*	Is the fuel fill cover closed and locked?	Yes/No
*	Is the audible alarm for the generator in "normal" (silent) status? The inspector only needs to listen for the audible alarm – a chirping noise. If "no," call Facilities Management at 1-877-658-2181.	Yes/No
*	Is the spill response plan posted on the Emergency Generator? If no, print a copy, laminate, and post it near fuel fill port.	Yes/No
*	Is the tank free of excessive rust, peeling paint, or damage? If no, call Facilities Management at 1-877-658-2181.	Yes/No
*	Is the concrete foundation for the tank free of any damage or cracks? If no, call Facilities Management at 1-877-658-2181.	Yes/No
*	Is the tank fuel level gauge readable and in good condition?	Yes/No



## Facility/Site

LOWE'S #2211

811 East Arques Avenue

Sunnyvale, CA 94085

CERS ID

10416037

CAR000280123

## Submittal Status

Submitted on 5/21/2021 by *Maggie Ta* of Lowe's Home Centers, LLC (Mooresville, NC)

## APSA Facility Information

Conditionally Exempt APSA Tank Facility

N

Date Of SPCC Plan Certification or Date of 5-Year Review

8/23/2016

Total Aboveground Storage Capacity of  
Petroleum

Number of Tanks in Underground Area(s)

1500

1

**Appendix D:**

**811 East Arques  
Preventative  
Maintenance  
Checklist**



Type <b>PM</b>	Customer <b>Lowes - Primary</b>	Service Call ID <b>2112-04069</b>
Location - Address <b>2211 - 811 E Arques Ave Sunnyvale, CA</b>		PO / WO / AUTH / TRACKING <b>153764138</b>

### Equipment

Loca/Area	Unit	Type	Make	Model	Serial	Tons	Age	Rating	T-Stat
Electrical	1	PACKAGE UNIT	LENNOX	LCA036H2BN1Y	5605J18128	3.0	16	19	PROG
Entrance	2	PACKAGE UNIT	LENNOX	LGA120H2BH3G	5605K17185	10.0	16	19	EMS
Entrance	3	PACKAGE UNIT	LENNOX	LGA120H2BH3G	5605L02436	10.0	16	18	EMS
Sales	4	PACKAGE UNIT	LENNOX	LGA240H2BS3G	5605K02185	20.0	16	18	EMS
Sales	5	PACKAGE UNIT	LENNOX	LGC180H2BS2G	5605L02077	15.0	16	18	EMS
Sales	6	PACKAGE UNIT	LENNOX	LGA240H2BS3G	5605L02186	20.0	16	18	EMS
Sales	7	PACKAGE UNIT	LENNOX	LGA240H2BS3G	5605L02187	20.0	16	18	EMS
Sales	8	PACKAGE UNIT	LENNOX	LGC180H2BS2G	5605K13593	15.0	16	18	EMS
Sales	9	PACKAGE UNIT	LENNOX	LGC180H2BS2G	5605L02071	15.0	16	18	EMS
Sales	10	PACKAGE UNIT	LENNOX	LGC180H2BS2G	5605L02069	15.0	16	18	EMS
Sales	11	PACKAGE UNIT	LENNOX	LGC180H2BS2G	5605L02081	15.0	16	18	EMS
Sales	12	PACKAGE UNIT	LENNOX	LGC180H2BS2G	5605L02072	15.0	16	18	EMS
Sales	13	PACKAGE UNIT	LENNOX	LGC180H2BS2G	5605L02075	15.0	16	18	EMS
Sales	14	PACKAGE UNIT	LENNOX	LGC180H2BS2G	5605L02074	15.0	16	19	EMS
Sales	15	PACKAGE UNIT	LENNOX	LGC180H2BS2G	5605L02078	15.0	16	19	EMS
Sales	16	PACKAGE UNIT	LENNOX	LGC180H2BS2G	5605L02076	15.0	16	19	EMS
Sales	17	PACKAGE UNIT	LENNOX	LGC180H2BS2G	5605L02073	15.0	16	19	EMS
Sales	18	PACKAGE UNIT	LENNOX	LGC180H2BS2G	5605L02079	15.0	16	19	EMS
Receiving	19	PACKAGE UNIT	LENNOX	LGC180H2BS2G	5605L02070	15.0	16	19	EMS
Receiving	20	PACKAGE UNIT	LENNOX	LGC180H2BS2G	5605L02082	15.0	16	19	EMS

### Temperatures

Loca/Area	Unit	Type	Cooling				Heating		
			Outside	Mixed	Supply	Delta	Mixed	Supply	Delta
Electrical	1	PACKAGE UNIT	49	70	48	22	N/A	N/A	N/A
Entrance	2	PACKAGE UNIT	49	70	49	21	70	121	51
Entrance	3	PACKAGE UNIT	49	71	49	22	71	122	51
Sales	4	PACKAGE UNIT	49	70	48	22	70	120	50
Sales	5	PACKAGE UNIT	49	71	50	21	71	124	53
Sales	6	PACKAGE UNIT	49	71	124	53	71	122	51
Sales	7	PACKAGE UNIT	49	71	52	19	71	124	53
Sales	8	PACKAGE UNIT	49	71	53	18	71	125	54
Sales	9	PACKAGE UNIT	49	71	50	21	71	123	52
Sales	10	PACKAGE UNIT	49	71	51	20	71	122	51
Sales	11	PACKAGE UNIT	49	71	52	19	71	124	53
Sales	12	PACKAGE UNIT	49	71	52	19	71	124	53
Sales	13	PACKAGE UNIT	49	71	52	19	71	120	49
Sales	14	PACKAGE UNIT	49	71	49	22	71	118	47
Sales	15	PACKAGE UNIT	50	73	55	18	73	112	39
Sales	16	PACKAGE UNIT	50	72	52	20	72	106	34
Sales	17	PACKAGE UNIT	49	73	56	17	73	105	32

Customer Signature: \_\_\_\_\_

*Tina*  
49

MOD: TINA WOZNAK

Technician Signature: \_\_\_\_\_

*[Signature]*

4084 - JESSE GOMEZ



Type <b>PM</b>	Customer <b>Lowes - Primary</b>	Service Call ID <b>2112-04069</b>
Location - Address <b>2211 - 811 E Arques Ave Sunnyvale, CA</b>		PO / WO / AUTH / TRACKING <b>153764138</b>

Sales	18	PACKAGE UNIT	49	74	55	19	73	108	35
Receiving	19	PACKAGE UNIT	50	72	53	19	72	107	35
Receiving	20	PACKAGE UNIT	50	73	52	21	72	110	38

### Technicians Time

Name	Time In	Time Out	Total Time (h)
6369 - GEOVANY MUNOZ	12/27/2021 10:37 AM	12/27/2021 8:23 PM	9.75
4084 - JESSE GOMEZ	12/27/2021 11:08 AM	12/27/2021 7:15 PM	8.25

### Belts & Filters

Part Description	Unit														
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
BELT A43	1														
BELT A46			1												
BELT B51		1													
BELT B59					1			1	1	1	1	1	1	1	1
BELT B66				1		2	2								
PLEATED FILTER 16X25X2	2														
PLEATED FILTER 18X24X2		4	4												
PLEATED FILTER 24X24X2				6	6	6	6	6	6	6	6	6	6	6	6

Part Description	Unit				
	16	17	18	19	20
BELT B59	1	1	1	1	1
PLEATED FILTER 24X24X2	6	6	6	6	6

### Tasks

Task Name	Result	Completed On	Completed By
Did you replace the filters this visit?	DONE	12/27/2021 3:59 PM	6369
LENNOX S: 5605J18128	DONE	12/27/2021 4:00 PM	6369
LENNOX S: 5605K17185	DONE	12/27/2021 4:02 PM	6369
LENNOX S: 5605L02436	DONE	12/27/2021 4:03 PM	6369
LENNOX S: 5605K02185	DONE	12/27/2021 4:33 PM	6369
LENNOX S: 5605L02077	DONE	12/27/2021 4:34 PM	6369
LENNOX S: 5605L02186	DONE	12/27/2021 4:35 PM	6369
LENNOX S: 5605L02187	DONE	12/27/2021 4:36 PM	6369
LENNOX S: 5605K13593	DONE	12/27/2021 4:37 PM	6369
LENNOX S: 5605L02071	DONE	12/27/2021 4:38 PM	6369
LENNOX S: 5605L02069	DONE	12/27/2021 4:40 PM	6369
LENNOX S: 5605L02081	DONE	12/27/2021 4:42 PM	6369

Customer Signature:

*Tina*

MOD: TINA WOZNAK

Technician Signature:


*Jesse Gomez*

4084 - JESSE GOMEZ



Type <b>PM</b>	Customer <b>Lowes - Primary</b>	Service Call ID <b>2112-04069</b>
Location - Address <b>2211 - 811 E Arques Ave Sunnyvale, CA</b>		PO / WO / AUTH / TRACKING <b>153764138</b>

LENNOX S: 5605L02072	DONE	12/27/2021 4:43 PM	6369
LENNOX S: 5605L02075	DONE	12/27/2021 5:24 PM	6369
LENNOX S: 5605L02074	DONE	12/27/2021 5:25 PM	6369
LENNOX S: 5605L02078	DONE	12/27/2021 4:36 PM	4084
LENNOX S: 5605L02076	DONE	12/27/2021 4:34 PM	4084
LENNOX S: 5605L02073	DONE	12/27/2021 4:33 PM	4084
LENNOX S: 5605L02079	DONE	12/27/2021 4:32 PM	4084
LENNOX S: 5605L02070	DONE	12/27/2021 4:31 PM	4084
LENNOX S: 5605L02082	DONE	12/27/2021 4:29 PM	4084
Did you call the IVR to check in: IVR number: Call 516-500-7776	DONE	12/27/2021 2:17 PM	4084
Completing this task will automatically IVR you into	DONE	12/27/2021 2:16 PM	4084
Completing this task will IVR you out of ServiceChannel. You must	DONE	12/27/2021 4:42 PM	4084
Did you review the Risk Assessment at this job site?	DONE	12/27/2021 2:16 PM	4084
Did you check in with the store manager? Enter store manager's	TINA WOZNIAK	12/27/2021 4:39 PM	4084
Did you call the IVR to check out: IVR number: Call 516-500-7776	DONE	12/27/2021 5:25 PM	6369
Enter store manager's first name:	TINA	12/27/2021 4:39 PM	4084
Enter store manager's last name:	WOZNIAK	12/27/2021 4:39 PM	4084
I certify I have neither received or witnessed any job related	I DID NOT WITNESS	12/27/2021 8:23 PM	6369
I certify I have neither received or witnessed any job related	I DID NOT WITNESS	12/27/2021 7:07 PM	4084


Customer Signature:   
MOD: TINA WOZNIAK

Technician Signature:   
4084 - JESSE GOMEZ



Type <b>PM</b>	Customer <b>Lowes - Primary</b>	Service Call ID <b>2112-04069</b>
Location - Address <b>2211 - 811 E Arques Ave Sunnyvale, CA</b>		PO / WO / AUTH / TRACKING <b>153764138</b>

		Unit														
Section	Checkpoint	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
Age	<b>Age*</b>	Poor	Poor	Poor	Poor	Poor	Poor	Poor	Poor	Poor	Poor	Poor	Poor	Poor	Poor	Poor
Cabinet	<b>Cabinet/Paint*</b>	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Outdoor Air Screen	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Panels Insulation	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
Condensing	<b>Compressor*</b>	Fair														
	Compressor #1		Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Compressor #2		Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Compressor #3				Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Compressor #4				Fair		Fair	Fair								
	<b>Condenser Coil*</b>	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Condenser Fan #1		Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Condenser Fan #2		Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Condenser Fan #3				Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Condenser Fan #4				Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Condenser Fans	Fair														
	Drier Condition	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Visual Leak	DNE	DNE	DNE	Fair	Fair	Fair	DNE	DNE	DNE	DNE	Fair	Fair	Fair	Fair	Fair
	Economizer	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
Electrical	Damper Blades and Connectors	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Economizer Controls	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Economizer Motor	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Sensors	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Disconnect Fuses	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
Fan	Safety Controls	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good
	T-Stat/ EMS	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Unit Controls	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Wiring	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Belts and Pulleys	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Blower Wheel Bearing	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Drain Pan	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	<b>Duct System*</b>	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	<b>Evap Motor*</b>	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	<b>Evaporator Coil*</b>	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
Heating	Filters	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good
	<b>Heat. Exg./Burners/Elec.</b>	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Ignition Controls	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good
Service Area	Operational Control Valves	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good	Good
	ACR Piping/Insulation	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	Condensate Drain	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair
	<b>Curbs &amp; Stands*</b>	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair	Fair

Customer Signature: 

MOD: TINA WOZNIAK

Technician Signature:   
4084 - JESSE GOMEZ




Type <b>PM</b>	Customer <b>Lowes - Primary</b>	Service Call ID <b>2112-04069</b>
Location - Address <b>2211 - 811 E Arques Ave Sunnyvale, CA</b>		PO / WO / AUTH / TRACKING <b>153764138</b>

Service Area Debris      Good Good Good Good Good Good Good Good Good Good Good Good Good Good Good Good

\* These checkpoints are unit ratings.

Customer Signature: Tina  
MOD: TINA WOZNAK

Technician Signature: Jesse Gomez  
4084 - JESSE GOMEZ



PO / WO / AUTH / TRACKING  
153764138

Location - Address

**2211 - 811 E Arques Ave Sunnyvale, CA**

		Unit									
Section	Checkpoint	16	17	18	19	20					
Age	Age*	Poor	Poor	Poor	Poor	Poor					
Cabinet	Cabinet/Paint*	Fair	Fair	Fair	Fair	Fair					
	Outdoor Air Screen	Fair	Fair	Fair	Fair	Fair					
	Panels Insulation	Fair	Fair	Fair	Fair	Fair					
Condensing	Compressor #1	Fair	Fair	Fair	Fair	Fair					
	Compressor #2	Fair	Fair	Fair	Fair	Fair					
	Compressor #3	Fair	Fair	Fair	Fair	Fair					
	Condenser Coil*	Fair	Fair	Fair	Fair	Fair					
	Condenser Fan #1	Fair	Fair	Fair	Fair	Fair					
	Condenser Fan #2	Fair	Fair	Fair	Fair	Fair					
	Condenser Fan #3	Fair	Fair	Fair	Fair	Fair					
	Condenser Fan #4	Fair	Fair	Fair	Fair	Fair					
	Drier Condition	Fair	Fair	Fair	Fair	Fair					
	Visual Leak	Fair	DNE	DNE	DNE	DNE					
Economizer	Damper Blades and Connectors	Fair	Fair	Fair	Fair	Fair					
	Economizer Controls	Fair	Fair	Fair	Fair	Fair					
	Economizer Motor	Fair	Fair	Fair	Fair	Fair					
	Sensors	Fair	Fair	Fair	Fair	Fair					
Electrical	Disconnect Fuses	Fair	Fair	Fair	Fair	Fair					
	Safety Controls	Good	Good	Good	Good	Good					
	T-Stat/ EMS	Fair	Fair	Fair	Fair	Fair					
	Unit Controls	Fair	Fair	Fair	Fair	Fair					
	Wiring	Fair	Fair	Fair	Fair	Fair					
Fan	Belts and Pulleys	Fair	Fair	Fair	Fair	Fair					
	Blower Wheel Bearing	Fair	Fair	Fair	Fair	Fair					
	Drain Pan	Fair	Fair	Fair	Fair	Fair					
	Duct System*	Fair	Fair	Fair	Fair	Fair					
	Evap Motor*	Fair	Fair	Fair	Fair	Fair					
	Evaporator Coil*	Fair	Fair	Fair	Fair	Fair					
	Filters	Good	Good	Good	Good	Good					
Heating	Heat. Exg./Burners/Elec.	Fair	Fair	Fair	Fair	Fair					
	Ignition Controls	Good	Good	Good	Good	Poor					
	Operational Control Valves	Good	Good	Good	Good	Good					
Service Area	ACR Piping/Insulation	Fair	Fair	Fair	Fair	Fair					
	Condensate Drain	Fair	Fair	Fair	Fair	Fair					
	Curbs & Stands*	Fair	Fair	Fair	Fair	Fair					
	Debris	Good	Good	Good	Good	Good					

\* These checkpoints are unit ratings.

Customer Signature:

7/Na<sub>49</sub>

MOD: TINA WOZNIAK



Technician Signature:

4084 - JESSE GOMEZ



## Appendix E:

### Vapor Pin Installation Standard Operating Procedure




# Standard Operating Procedures

## Subslab Vapor Pin Installation

# Certification

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I have no personal knowledge that the information submitted is other than true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.



---

J. Wesley Hawthorne

13 September 2022

---

Date

# Table of Contents

LIST OF ATTACHMENTS..... iii

LIST OF APPENDICES..... IV

LIST OF ACRONYMS AND ABBREVIATIONS ..... V

1. Introduction ..... 1

2. Subslab Vapor Pin Installation ..... 2

    2.1 The Vapor Pin Overview..... 2

    2.2 Required Tools ..... 2

    2.3 Installation Procedures ..... 3

    2.4 Decommissioning Procedures..... 5

References ..... 7

**ATTACHMENTS**

**ABBREVIATIONS**

## LIST OF ATTACHMENTS

### ATTACHEMNT

<u>NO.</u>	<u>TITLE</u>
1	The Vapor Pin
2	Drawing of Installed Vapor Pin

## LIST OF ACRONYMS AND ABBREVIATIONS

<u>ACRONYM</u>	<u>DESCRIPTION</u>
DTSC	Department of Toxic Substances Control
EPA	United States Environmental Protection Agency
In. H <sub>2</sub> O	Inches of Water Column
In. Hg	Inches of Mercury
L	Liter
Locus	Locus Technologies
mg/L	Milligrams per Liter
RWQCB	Regional Water Quality Control Board
SOP	Standard Operating Procedure

## 1. Introduction

This Standard Operating Procedure (SOP) was prepared by Locus Technologies (Locus) to support subslab vapor pin installation. As such, this document outlines the procedures and site-specific considerations to be implemented during forthcoming vapor pin installations. All activities described in this document will be compliant with the 2015 *Advisory Active Soil Gas Investigations* guidance, which was jointly developed by California Department of Toxic Substances Control (DTSC) and California Regional Water Quality Control Board (RWQCB) (EPA, 2015).

## 2. Subslab Vapor Pin Installation

To characterize the subslab vapor at potentially impacted sites, subslab Vapor Pins (Cox–Colvin, 2022) will be installed. This section describes the vapor pin installation procedures to be utilized. See the soil gas sampling SOP for sampling procedures.

### 2.1 The Vapor Pin Overview

The Vapor Pin, manufactured by Cox–Colvin & Associates, is a sampling device designed to aid in collecting soil vapor samples from directly beneath a building floor. As a general overview, the Vapor Pin is a hollow, single piece of stainless steel that is barbed at both ends and threaded at the union of the two barbs (Attachment 1). The entire length of the Vapor Pin is 3.22 inches. The long and wider barbed end is covered with a silicon sleeve, which then is hammered into a hole previously installed into the slab of a building. The silicon around this barb compresses against the circumference of the hole as it is hammered in, to form an air-tight seal between the air above and below the slab. The smaller and shorter barb is the sample port of the Vapor Pin, from which sampling equipment can be attached. The threads at the center of the Vapor Pin are used to attached flush-to-grade cover. Each component can be seen in Attachment 2. Adoption of vapor pin technology for vapor intrusion investigations has been encouraged by the DTSC, provided sampling techniques from the 2015 guidance are considered and implemented (EPA, 2015).

### 2.2 Required Tools

The following tools and/or equipment will be used to install each Vapor Pin:



- ◇ Vapor Pin Sampling Kit (<https://www.vaporpin.com/product/vapor-pin-sampling-device-sets/>)
- ◇ Vapor Pin Drilling Guide (<https://www.vaporpin.com/product/stainless-steel-drilling-guide/>)
- ◇ Vapor Pin Installation Tool  
(<https://www.vaporpin.com/product/installationextraction-tool/>)
- ◇ Rotary Hammer Drill
- ◇ 1½-inch diameter hammer drill bit
- ◇ 5⁄8-inch diameter hammer drill bit
- ◇ Diamond hole saw
- ◇ ¾-inch diameter bottle brush
- ◇ Dead blow hammer
- ◇ Utility Vacuum

## 2.3 Installation Procedures

Before starting the Vapor Pins installations, a utility locator will be contracted to clear proposed locations for subslab utilities such as water, sewer, and electrical conduits. The locator will also be used to ensure any reinforcement structures within the slab, such as rebar, will not be encountered during installations. Following successful clearance at each location, the Vapor Pins will be installed using the following steps:

1. A utility vacuum, such as a Shop-Vac, will be set up near the Vapor Pin location to collect drill cuttings as the location is drilled. During vacuum use, the area will be monitored for potential dust. Shall dust be observed, drilling will be

temporarily ceased and masks provided to prevent airborne dust from reaching field staff and nearby receptors.

2. Using the rotary hammer drill with the 1½-inch diameter hammer drill bit attached, a 1½-inch diameter hole will be drilled 1¾ inches deep. If drilling through tile is necessary, a diamond hole saw first will be used to cut through the layer of tile to eliminate any stress on the surrounding tile area. This depth will be confirmed by placing the Vapor Pin drilling guide in this initial hole. This tool will sit flush with the slab surface when placed in the initial hole is the appropriate depth.
3. With the Vapor Pin drilling guide still in the initial hole, a ⅝-inch diameter hole will be drilled through the remaining depth of the slab. This will be done using the rotary hammer drill with the ⅝-inch diameter hammer drill bit attached. The drill bit will be centralized using the Vapor Pin drilling guide. The drill bit will be advanced three to four inches into the engineering fill below the slab. During this step, cautionary measures, such as slow drill speeds and careful observation of drill depth, will be taken to minimize any potential damage that could be incurred to the moisture barrier underlying the slab. Should any damage occur to the moisture barrier during any of the installations, it will be documented and an attempt to repair will be made upon destruction of the Vapor Pin.
4. Once a hole has successfully been drilled through the slab, the hole will be cleaned with the bottle brush. All loose cuttings will be removed with the vacuum thereafter.
5. A silicon sleeve will be installed over the barbs of the downward end of the Vapor Pin to create a seal. The Vapor Pin will then be placed into the ⅝-inch

diameter hole and the Vapor Pin installation tool will be placed on top of the sample (upward) barb. This tool protects the barb as it is hammered into the  $\frac{5}{8}$ -inch hole.

6. Using a dead blow hammer, the Vapor Pin will be tapped into the  $\frac{5}{8}$ -inch hole until the bottom of the threads are flush with the  $\frac{5}{8}$ -inch hole surface. An indication of a good seal is observed when the silicon sleeve forms a slight budge between the slab and the Vapor Pin shoulder. During this step, care will be taken to ensure that the installation tool is aligned parallel with the Vapor Pin to avoid damage.
7. A cap will be placed on the tip of the sampling barb and a flush-mounted cover will be threaded onto the Vapor Pin. The Vapor Pin is now installed. Once subslab vapors have re-equilibrated, at least two hours following installation, the locations may be sampled.

## 2.4 Decommissioning Procedures

After successful completion of the sampling program, the subslab Vapor Pins will be decommissioned according to the following procedures:

1. The flush-mounted cover and protective cap will be removed from the Vapor Pin.
2. The Vapor Pin Installation Tool will be threaded onto the Vapor Pin. Once the tool is securely threaded onto the Vapor Pin, the tool will continue to be turned clockwise. The Vapor Pin will extract from the hole like a wine cork. The manufacturer explicitly states not to pull on the Vapor Pin.

3. Once the Vapor Pin has been fully removed, the location will be re-inspected for damage to the subslab moisture barrier, if one is present. Should any damage have occurred, the  $\frac{5}{8}$ -inch hole will be re-drilled to a depth of 6 inches below the slab to create a void in the fill below the slab. A  $\frac{5}{8}$ -inch tube will be inserted to the bottom of the hole, and silicon will be pressure injected into the hole while slowly removing the tube. The injection will end at where the  $\frac{5}{8}$ -inch hole widens to the  $1\frac{1}{2}$ -inch diameter hole. This will create a seal where the moisture barrier has been punctured.
4. The remaining  $1\frac{3}{4}$  inches to the slab surface will be backfilled with neat cement grout. A putty knife will be used to remove any excess grout and ensure the original surface is restored.

## References

California Environmental Protection Agency, 2015, *Advisory Active Soil Gas Investigations*, July.


# ATTACHMENTS

## Attachment 1. The Vapor Pin



Cox-Colvin, 2022

## Attachment 2. Drawing of Installed Vapor Pin



Cox-Colvin, 2022





## Appendix F:

### Summa Canister Sampling Standard Operating Procedure




# Standard Operating Procedure

## Soil Gas Sampling using 1-Liter Summa Canisters

# Certification

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I have no personal knowledge that the information submitted is other than true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.



---

J. Wesley Hawthorne

13 September 2022

---

Date

# Table of Contents

LIST OF ATTACHMENTS.....	iii
LIST OF APPENDICES.....	IV
LIST OF ACRONYMS AND ABBREVIATIONS .....	V
1. Introduction .....	1
2. Soil Gas Sampling Procedures .....	2
2.1 Sampling Equipment .....	2
2.2 Sampling Conditions .....	3
2.3 Sample Collection Procedures .....	3
2.3.1 Sample Apparatus Construction .....	3
2.3.2 Shut-In Test.....	4
2.3.3 Purge and Leak Test.....	5
2.3.4 Sample Collection .....	6
References .....	7

## ATTACHMENTS

## ABBREVIATIONS

LIST OF ATTACHMENTS
---------------------

<u>ATTACHMENT</u>	<u>TITLE</u>
1	Soil Vapor Sampling Components
2	Soil Vapor Sampling Form

## LIST OF ACRONYMS AND ABBREVIATIONS

<u>ACRONYM</u>	<u>DESCRIPTION</u>
DTSC	Department of Toxic Substances Control
EPA	United States Environmental Protection Agency
In. H <sub>2</sub> O	Inches of Water Column
In. Hg	Inches of Mercury
L	Liter
Locus	Locus Technologies
mg/L	Milligrams per Liter
RWQCB	Regional Water Quality Control Board
SOP	Standard Operating Procedure

## 1. Introduction

This Standard Operating Procedure (SOP) was prepared by Locus Technologies (Locus) to support soil gas sampling. As such, this document outlines the procedures and site-specific considerations to be implemented during forthcoming sampling events. All activities described in this document will be compliant with the 2015 *Advisory Active Soil Gas Investigations* guidance, which was jointly developed by California Department of Toxic Substances Control (DTSC) and California Regional Water Quality Control Board (RWQCB) (EPA, 2015).

## 2. Soil Gas Sampling Procedures

This section discusses the methods and reporting procedures to be used for soil gas sampling. The procedure was developed for sampling sub slab vapor pins but also can be used for gathering samples from soil gas probes.

### 2.1 Sampling Equipment

Soil gas sampling equipment will be implemented in accordance with DTSC and RWQCB guidance (EPA, 2015). Each monitoring location will be purged with a flow-regulated vacuum pump. Both purging and sampling will occur within a shroud that will contain a constant ambient concentration of 20 percent (%) helium in order to check for communication between the surface air and vapors at depth. Ambient helium in the shroud will be measured using a standard helium gas detector, such as the C-Squared He Analyzer. Samples will be collected into passivated 1-liter (L) Summa canisters. Attachment 1 presents the components of a typical soil vapor sample apparatus. The main components of the shroud and sampling set-up are as follows:

- ◇ 1-Liter passivated stainless-steel Summa canister
- ◇ Sample manifold, which includes:
  - ◇ Cannister vacuum gauge
  - ◇ Flow regulator (flowrate not to exceed 200 mL/min)
  - ◇ Well-head vacuum gauge
  - ◇ Shut-off valve to purge line
- ◇ Vacuum pump



- ◇ Tracer gas shroud
- ◇ Tracer gas (Helium)
- ◇ Field helium detectors (for measuring helium in the shroud and in collected purge air)

## 2.2 Sampling Conditions

Moisture conditions in the field can affect the ability to collect unbiased soil vapor samples. For instance, rainfall decreases the air-filled porosity of shallow soils, thereby limiting diffusional transport of subsurface gases. Also, constituents in soil vapor may partition into clean infiltrating rainwater when shallow soils are saturated. These areas of high soil moisture that become saturated following precipitation events should be allowed to drain, if possible, prior to soil vapor sampling. As such and per the DTSC guidance, soil gas sampling will not occur during a significant rain event and will only occur after five days without a significant rain event (EPA, 2015). DTSC defines a significant rain event as 0.5 inches of rainfall occurring during a 24-hour period.

## 2.3 Sample Collection Procedures

### 2.3.1 *Sample Apparatus Construction*

At each sample location, sampling apparatus will be completely set up to allow for shut-in testing, leak testing, purging, and sampling. Initially, a 1 L Summa canister will be connected to a laboratory-supplied sample manifold that includes a flow-regulator that restricts flow between 100 and 200 milliliters, and does not exceed 200 mL/min. The unique identification numbers associated with both the cannister and with the manifold will be recorded on field sampling forms and on the chain-of-custody for

each sample location. An example sampling form is included in Attachment 2. A new sample manifold will be used at each location. After successful shut-in testing, sample tubing will be connected to the monitoring location barb using semi-rigid tubing. The purge line will then be connected to the Summa canister manifold using ferrule fittings and a compression nut. A vacuum pump, with both inlet and outlet barbs, will then be fastened to the outlet of the canister manifold. A last length of tubing will be attached to the outlet barb of the vacuum pump so that air purged from the sample location can be collected into a Tedlar bag to ensure soil gas is not released into the indoor air and for leak testing the sample train. A helium detector will be placed immediately next to the cannister, near the sampling location. A shroud is then placed over the entire sampling apparatus, excluding only the vacuum pump and Tedlar bag, to serve as an enclosure. Helium gas will be introduced into the shroud from a small hole in the enclosure that allows tubing to enter from a flow-regulated helium tank.

### *2.3.2 Shut-In Test*

Prior to collection of samples, quantitative shut-in tests will be conducted in accordance with regulatory guidance (EPA, 2015). The shut-in test involves applying a minimum vacuum of 100 inches of water column (in. H<sub>2</sub>O) to the sample train with a vacuum pump to evacuate the lines. A shut-off valve to the vacuum pump will then be closed and the sampling train will remain under vacuum for approximately one minute to assess whether there was any loss of vacuum. If there is any observable loss of vacuum, the fittings will be adjusted until the vacuum in the sample train does not noticeably dissipate. After the shut-in test is successfully completed, the result will be record on field sampling forms and the sampling train will not be altered.

### 2.3.3 *Purge and Leak Test*

Following a successful shut-in test, each sample location will be purged. Purging is required to remove ambient air from the sample point and sampling train. In accordance with the *Soil Gas Advisory*, a standard three volume purge will be used for each soil gas sample location. The purge volume will be calculated using standard methods to account for the volume of stagnant air in each sample location as well as the sample tubing and sample manifold. Dimensions will be gathered from construction drawings or by field measurements. Sample location will be purged at a flow rate between 100 and 200 milliliters per minute (mL/min) at a maintained vacuum of 100 in. H<sub>2</sub>O or less.

During purging, quantitative leak tests will be conducted using helium as a gaseous tracer compound under a shroud. This method of leak detection ensures that soil vapor wells, probes, or pins are properly constructed, and the sample train components do not leak while in use. The shroud will contain the entire sampling apparatus and the sampling location annulus. A helium detector will be used to hold shroud helium concentrations at a minimum of 20% under the shroud. All purged air will be collected into a Tedlar bag, which will then be analyzed for helium outdoors after purging is complete to check for leaks in the sample train and to ensure potentially VOC-impacted purged air is not released into the indoor air. Samples will not be collected until the quantitative leak test demonstrates that leaks resulting in detections of helium are not present above the accepted maximum allowable concentration, which is 5 % of the average shroud helium concentration. Helium concentrations as well as canister and well-side vacuum measurements will be recorded at regular intervals during the purge on field sampling forms.

#### 2.3.4 *Sample Collection*


After three volumes have been purged, a shut-off valve to the vacuum pump will be closed and the pump will be turned off. Using this order of operations will prevent ambient air entering the cannister through the purge line as the purge line vacuum equilibrates with atmospheric pressure. The sample will then be collected by opening the cannister valve recording the initial canister vacuum pressure on field sampling forms and on the chain-of-custody. After this, the shroud will again be placed over the sample apparatus and helium will be maintained at a concentration of 20% under the enclosure. Laboratory analysis for helium by ASTM D1946 will be used to evaluate whether ambient air was introduced into the sample through the well seal or sampling apparatus seals during sample collection. The laboratory-provided sample manifold includes a flow regulator that restricts flow to between 100 and 200 mL/min (less than 200 mL/min) at a vacuum at 100 in. H<sub>2</sub>O or less. At regular intervals during sample collection, shroud helium concentration, well-side vacuum pressure, and cannister vacuum pressure will be recorded. Sample collection will cease with a slight vacuum to avoid diluting the sample. Once the canister vacuum gauges read between 8 and 4 inches of mercury (in. Hg), the canister valve will be closed. The cannister's final vacuum reading will be noted on field sampling forms and on the chain-of-custody to document sample integrity.

## References

California Environmental Protection Agency, 2015, *Advisory Active Soil Gas Investigations*, July.

# ATTACHMENTS

## Attachment 1. Soil Vapor Sampling Components



EPA, 2015, Fig. C-1

# Soil Gas Sampling Form





# Soil Vapor Field Measurement Log

Date:			Sampler:	
Client:			Project #:	
Container ID:			Manifold ID:	
Sample ID:			Temperature:	
Duplicate Sample ID:		Duplicate Container ID:		Precipitation:

## Shut-In Test Measurements

Start Time	Start Vacuum (inches Hg)	End Time	End Vacuum (inches Hg)	Shut-In Test Pass/Fail

## Purge and Leak Check Measurements

Calculated Purge Volume	Calculated Purge Time

Time	Flow (ml/min)	Well side Vacuum Pressure (inches Hg)	Canister Vacuum Pressure (inches Hg)	In-line Helium Concentration (%)	Shroud Helium Concentration (%)	Comments (purge method, issues, etc)

## Sampling Measurements

Time	Flow (ml/min)	Well side Vacuum Pressure (inches Hg)	Canister Vacuum Pressure (inches Hg)	Shroud Helium Concentration (%)	Comments
Average Helium Concentration:					

Notes



## Appendix G:

### City of Sunnyvale Sewer Utility Map

SUNNYVALE - SEWER



Legend

- Lines
- Active Sunnyvale Main
  - Abandoned Sunnyvale Main
  - Active Private Main
  - Others Main
  - Active Sunnyvale Lateral
  - Abandoned Sunnyvale Lateral
  - Active Private Lateral
  - Active Force Main
  - Abandoned Force Main
  - Active Santa Clara Main
  - Active Cupertino Main

- Points
- Flushing Inlet
  - Active Manhole
  - Abandoned Manhole
  - Active Drop Manhole
  - Diversion Structure
  - Grade Break
  - Main Line Clean Out
  - Network Structure
  - Clean Out
  - Active Plug
  - Abandoned Plug
  - Meter
  - Pump Station
  - Lift Station
  - Riser
  - Drain Inlet

- Polygons
- Easement
  - Concrete Casing
  - Steel Casing
  - Detail Polygon
  - Blockgrid
  - City Boundary

- Basemap
- Constructed Centerline
  - Street Centerline
  - Parcel

- Annotation
- |                      |                             |                       |                            |
|----------------------|-----------------------------|-----------------------|----------------------------|
| 365'                 | - Pipe Length               | BORREGAS AVENUE       | - Street Name              |
| 6"                   | - Diameter                  | 129                   | - Lot Number               |
| VCP                  | - Material                  | 1405                  | - Address Number           |
| 0.2%                 | - Slope                     | ONSITE PRIVATE SYSTEM | - Miscellaneous Annotation |
| US=19.48             | - Upstream Elevation        |                       |                            |
| DS=18.48             | - Downstream Elevation      |                       |                            |
| 209                  | - Manhole Number            |                       |                            |
| R=23.58              | - Rim Elevation             |                       |                            |
| 6" CO                | - Clean Out Annotation      |                       |                            |
| F.I.                 | - Flushing Inlet Annotation |                       |                            |
| 10' P.U.E            | - Easement Annotation       |                       |                            |
| 80'-42" Steel Casing | - Casing Annotation         |                       |                            |



411	412	413
390	389	388
371	372	373

389



Jan 15, 2020

